

Abstract | Zusammenfassung



Reihenhaus-Komplex mit vier Einheiten in Darmstadt-Kranichstein

Data of building | Gebäudedaten

Year of construction Baujahr	2024		
U-value external wall U-Wert Außenwand	0,137, 0.209, 0.234, 0.259 W/(m ² K)	Space heating Heizwärmebedarf	15 kWh/(m ² a)
U-value basement U-Wert Kellerdecke	N/A W/(m ² K)	Primary Energy Renewable (PER) Erneuerbare Primärenergie (PER)	49 kWh/(m ² a)
U-value roof U-Wert Dach	0,078, 0,125 W/(m ² K)	Generation of renewable Energy Erzeugung erneuerb. Energie	0 kWh/(m ² a)
U-value window U-Wert Fenster	0,95 W/(m ² K)	Non-renewable Primary Energy (PE) Nicht erneuerbare Primärenergie (PE)	124 kWh/(m ² a)
Heat recovery Wärmerückgewinnung	77 %	Pressurization test n ₅₀ Drucktest n ₅₀	0,52 h ⁻¹
Special features Besonderheiten	Its predominate wall construction is clay poroton single skin block work which is acting also as the main insulating material.		

Brief Description

Passive House Darmstadt Kranichstein

Brook House is a four-storey social housing development located in Hamlin Gardens, Exeter. Designed by Gale & Snowden Architects for Exeter City Council, the scheme comprises 21 apartments (11 two-bedroom and 10 one-bedroom units) and reflects a strong commitment to sustainable design.

External wall U-values ranged from 0.222 to 0.259 W/m²K—slightly above typical Passivhaus benchmarks. However, the design team optimised performance by leveraging the region's milder climate and the building's compact form. Single-skin Poroton clay blocks were used as the primary insulated wall element, enhancing thermal efficiency.

The building is split into two wings, each serviced by a Nilan Compact P combi unit. This integrated system provides ventilation, space heating, and domestic hot water via a micro air-source heat pump, offering an efficient and compact solution for each apartment.

Responsible project participants

Verantwortliche Projektbeteiligte

Architect Entwurfsverfasser	Lawrence Millyard Gale & Snowden Architects www.ecodesign.co.uk
Implementation planning Ausführungsplanung	
Building systems Haustechnik	Jason Fitzsimmons Gale & Snowden Architects www.ecodesign.co.uk
Structural engineering Baustatik	-
Building physics / Passivhaus designer Bauphysik	Jason Fitzsimmons Gale & Snowden Architects www.ecodesign.co.uk
Passive House project planning Passivhaus-Projektierung	Jason Fitzsimmons Gale & Snowden Architects www.ecodesign.co.uk
Construction management Bauleitung	Nevada Construction

Certifying body

Zertifizierungsstelle

Passivhaus Institut Darmstadt www.passiv.de	WARM
---	------

Certification ID

Zertifizierungs ID

7792	Project-ID (www.passivehouse-database.org) Projekt-ID https://passivehouse-database.org/index.php?lang=en#d_7792
------	---

Author of project documentation

Passivhaus Institut Darmstadt www.passiv.de	
Date Datum	Signature Unterschrift
10/06/24	<i>J Fitzsimmons</i>

1. Ansichtsfotos

© Passive House Institute




North East top floor



2. Innenfoto exemplarisch


Landlords area






3. Schnittzeichnung

Note all architectural details / drawings provided herein were developed by Gale & Snowden Architects



© Passive House Institute




1

Building Section BB


1:50 2

Building Section CC

1:50



1 Building Section DD



2 Building Section EE 1:50




1

Building Section FF

1:50


4. Grundrisse

The following general arrangements show the architectural layouts, for the scheme consisting of 21 flats which span from north to south. The building is split into 2 zones. The green areas highlight common stairwells and lifts zone.




Ground Floor

1:50




First Floor

1:50



Second Floor

1:50




TF-Top of Screed

1:50

5. Konstruktion der Bodenplatte

The floor construction consisted of beam and block floor with concrete topping which formed the air tight layer at ground level. Ground insulation consisted of 250mm sitting on top of the concrete topping layer.



architects - engineers
integrated sustainable design
mechanical engineering
renovable engineering
energy modelling
healthy building design
performance design
research & development

Copyright in all the material on this sheet vests in the Architects who assert their right to be identified as the author of the material in accordance with the Copyright, Designs and Patents Act 1988. The material may not be copied under any circumstances for any purpose without the express written permission of the Architects.

- T1 Tender Issue 09/01/2018
- C1 Construction Issue for Contract and Building Regulation Notification 09/01/2018
- C2 Construction Meeting
- C3 Meeting Issue
- C4 14/12/17 External step bed note amended
- C5 15/02/22 Blockwork to site of Porotherm block amended
- C6 18/02/22 Concrete blockwork amended for Contractor

Notes

- Level varies. Refer to Landscape Architect information.
- 150 min GL - DPC

Render above DPC M20195 - Appendix by Aliscoo

Render below DPC M20195 - Appendix by Aliscoo

Preformed DPC F30270

DPC F30331

Mortar F30110

Concrete Overlay

Solid Masonry / Trenchblock to be agreed with EE

Autoclaved aerated concrete blockwork F10091

Dense concrete blockwork F10090

DPC F30330

Concrete fill blocks F30010

PC beam and block flooring beams F30010

DPM M20140

Concrete topping min 65mm (airtightness layer) M10110-250210

EPS insulation P10140

Airtight seal 250210

FE slip membrane

Fiber Screed, min 65mm M10115

Floor tiling M20110, 125 depending on location

FFL Datum Top of Served

Plaster and skim M20220

Porotherm clay block F10261

Blistering F20100A

Rigid insulation P10142

Mortar leveling bed

EPS insulation P10141

Render above DPC M20195 - Appendix by Aliscoo

Render step detail to Aliscoo detail and specification

DPC F30200

Mortar leveling bed

EPS insulation P10141

Render above DPC M20195 - Appendix by Aliscoo

Render step detail to Aliscoo detail and specification

DPC F30200

Mortar leveling bed

EPS insulation P10141

Render above DPC M20195 - Appendix by Aliscoo

Render step detail to Aliscoo detail and specification

DPC F30200

Mortar leveling bed

EPS insulation P10141

Render above DPC M20195 - Appendix by Aliscoo

Render step detail to Aliscoo detail and specification

DPC F30200

Mortar leveling bed

EPS insulation P10141

Render above DPC M20195 - Appendix by Aliscoo

Render step detail to Aliscoo detail and specification

DPC F30200

Mortar leveling bed

EPS insulation P10141

Render above DPC M20195 - Appendix by Aliscoo

Render step detail to Aliscoo detail and specification

DPC F30200

Mortar leveling bed

EPS insulation P10141

Render above DPC M20195 - Appendix by Aliscoo

Render step detail to Aliscoo detail and specification

DPC F30200

Mortar leveling bed

EPS insulation P10141

Render above DPC M20195 - Appendix by Aliscoo

Render step detail to Aliscoo detail and specification

DPC F30200

Mortar leveling bed


EPS insulation P10141

EXETER CITY COUNCIL - HAMLIN GARDENS

External Wall Ground Floor Junction
 Issued to: **OB/MS** from: **1.5 @ A3**
 Checked by: **CR** Date: **12.07.2019**
 Drawing No: **E1206-GSA-HG-DR-A-3000**
 Issue


Bideford Office Exeter Office
 18 Market Place Exeter Bank Chambers
 Bideford PL6 8JH 67 High Street
 Devon Exeter
 E3 9R 2DR Devon
 Tel: 01327 416602 Tel: 01392 719201
 Fax: 01327 425589 Fax: 01392 219059
 www.ecodesign.co.uk info@ecodesign.co.uk

RIBA Chartered Practice
 Directors: D Gale L Millyard I Snowden




6. Konstruktion der Außenwände

The walls consisted of proton clay blocks on the ground, first and second floors and timber frame on the 3rd top floor. For structural reasons 3 different proton block types were used. Typical clay block detail is shown to the right with site images below. The proton blocks provided a number of advantages – speed of construction, single skin construction with render and plaster on in the inside forming the air tight layer. The resulted in reduced materials and trades and a very simple to execute thermal and robust air tight line. Plus the product is very low in embodied carbon.



Timber frame wall detail at roof level



Calculation SommerGlobal


Project: 2024_09_30

Position: 01

Layer composition (outside to inside)

Number BE Description

Number	BE	Description	mm
1		Float ExtraClear	3,00
2		Saflex® Clear	0,76
3		Float ExtraClear	3,00
4	2	ClimaGuard Premium2 (εn=3%)	
5		90% Argon	16,00
6		EUROFLOAT	4,00
7	4	Matelux (εn=89%)	
8		90% Argon	16,00
9	5	ClimaGuard Premium2 (εn=3%)	
10		Float ExtraClear	3,00
11		Saflex® Clear	0,38
12		Float ExtraClear	3,00
			49,14



Transmission, reflexion, absorption

$\rho_v = 0,1439$ (external light reflectance)

$\rho'_v = 0,1535$ (internal light reflectance)

$\rho_e = 0,2565$ (solar direct reflectance outside)

$\rho'_e = 0,2726$ (solar direct reflectance inside)

α_e 1 = 0,2252; 3 = 0,0496; 5 = 0,0504 (solar direct absorptance)

$T_{UV} = 0,0000$ (ultraviolet transmittance)

$T_V = 0,7210$ (light transmittance)

$T_e = 0,4183$ (solar direct transmittance)

$R_a = 96,36$ (general color rendering index (CRI))

EN 410

SC = 0,5674 (Shading Coefficient, g/0,87)

b-Faktor = 0,6170 (VDI 2078, g/0,80)

$q_i = 0,0753$ (secondary heat inside)

$g = 0,4936$ (solar heat gain coefficient)

EN 673 Installation angle = 90° vertical

$U_g = 0,5713 \text{ W/m}^2\text{K}$ (Heat transfer coefficient)
Corrected emissivity according to EN 12898:2019

EN ISO 52022-3 $T_e = 5,00 \text{ }^\circ\text{C}$ $T_i = 20,00 \text{ }^\circ\text{C}$

$E_s = 300,00 \text{ W/m}^2$ System height = 1,50 m

$g_{th} = 0,0440$ (Thermal radiation factor)


$h_{c,e} = 18,00 \text{ W/m}^2\text{K}$ $h_{c,i} = 3,60 \text{ W/m}^2\text{K}$

$g_c = 0,0333$ (Convection factor)

$q_i = 0,0773$ (secondary heat inside)

$g_v = 0,0000$ (Ventilation factor)

$g_{tot} = 0,4956$ (solar heat gain coefficient)





9. Beschreibung der luftdichten Hülle

Building on experience from previous Passivhaus social housing projects with Exeter City Council, Gale & Snowden adopted a straightforward airtightness strategy for Hamlin Gardens: a direct plaster skim applied to the internal face of the Poroton clay blocks.

This plaster layer connected seamlessly to the concrete ground floor slab and to smart ply at roof level. Airtightness tapes were used to seal window junctions and service penetrations. The approach offered multiple benefits: it aligned well with the single-skin Poroton block construction, eliminated the need for additional insulation or airtightness membranes, reduced the number of trades and construction complexity, and lowered material use. Combined with the inherently low embodied carbon of the clay blocks, this strategy significantly reduced the project's overall embodied carbon footprint.

At roof level, smart ply was used as the airtightness barrier—a decision informed by lessons from previous projects where membrane-based solutions proved unreliable. Membranes often posed challenges in securing airtightness tapes due to their flexibility and tendency to shift. In contrast, the rigid smart ply provided a stable surface, allowing tapes to be applied securely and remain fixed, even under pressure testing. This approach ensured a more robust and durable airtight seal.



Block 1 air test result

Results			
Direction:	Pressurise	+	Depressurise
UCRN:	11542923		11542922
Air Flow Coefficient (C_{env}):	36.364		100.012
Air Leakage at 50 Pa (Q_{50}):	798.847		866.197
Air Flow Exponent (n):	0.79		0.55
Coefficient of Determination (r^2):	0.991		0.983

Air Permeability				Pass
Target:	≤ 10.00	$m^3 \cdot h^{-1} \cdot m^2 @ 50Pa$	0.82 $m^3 \cdot h^{-1} \cdot m^2 @ 50Pa$	✓
Pressurisation Test:	+	0.79 $m^3 \cdot h^{-1} \cdot m^2 @ 50Pa$		
Depressurisation Test:	-	0.85 $m^3 \cdot h^{-1} \cdot m^2 @ 50Pa$		

Air Changes Per Hour				Pass
Target:	≤ 0.6	$m^3 \cdot h^{-1} \cdot m^3 @ 50Pa$	0.51 $m^3 \cdot h^{-1} \cdot m^3 @ 50Pa$	✓
Pressurisation Test:	+	0.49 $m^3 \cdot h^{-1} \cdot m^3 @ 50Pa$		
Depressurisation Test:	-	0.53 $m^3 \cdot h^{-1} \cdot m^3 @ 50Pa$		

Block 2 air test result

Results			
Direction:	Pressurise	+	Depressurise
UCRN:	11542921		11542920
Air Flow Coefficient (C_{env}):	41.002		51.974
Air Leakage at 50 Pa (Q_{50}):	855.596		881.386
Air Flow Exponent (n):	0.78		0.72
Coefficient of Determination (r^2):	0.995		0.991

Air Permeability				Pass
Target:	≤ 10.00	$m^3 \cdot h^{-1} \cdot m^2 @ 50Pa$	0.88 $m^3 \cdot h^{-1} \cdot m^2 @ 50Pa$	✓
Pressurisation Test:	+	0.86 $m^3 \cdot h^{-1} \cdot m^2 @ 50Pa$		
Depressurisation Test:	-	0.89 $m^3 \cdot h^{-1} \cdot m^2 @ 50Pa$		

Air Changes Per Hour				Pass
Target:	≤ 0.6	$m^3 \cdot h^{-1} \cdot m^3 @ 50Pa$	0.53 $m^3 \cdot h^{-1} \cdot m^3 @ 50Pa$	✓
Pressurisation Test:	+	0.52 $m^3 \cdot h^{-1} \cdot m^3 @ 50Pa$		
Depressurisation Test:	-	0.54 $m^3 \cdot h^{-1} \cdot m^3 @ 50Pa$		

10. Lüftungsgerät

Ventilation, heating, and hot water at Hamlin Gardens are provided by a Nilan Compact P combi unit in each apartment. This system integrates mechanical ventilation with heat recovery (MVHR) and a micro air-source heat pump, delivering both heated air and domestic hot water efficiently.

The Nilan unit was selected as a simple, cost-effective solution that avoided the drawbacks of alternative approaches. A centralised system was considered but ruled out due to long pipe runs from the roof, associated heat losses, and the need for tenants to commit to a shared energy contract—something the council wished to avoid. Individual external air-source heat pumps were also discounted due to challenges with installation on a multi-storey building, as well as concerns over aesthetics, noise, and future maintenance.

The Nilan Compact P offered an all-in-one, low-impact solution ideally suited to the project's design and operational goals.

Ventilation, heating and hot water was via Nilan compact P combi MVHR unit with micro air source heat pump delivering heated air and hot water


Thermal Comfort:	$\theta_{\text{supply air}} \geq 16,5^{\circ}\text{C}$
Heat Recovery of ventilation system:	$\eta_{\text{WRG,eff}} \geq 75\%$
Electric efficiency ventilation system:	$P_{\text{el}} \leq 0,45 \text{ Wh/m}^3$
Air tightness (internal/external):	$V_{\text{Leakage}} \leq 3\%$
Total Primary Energy Demand (**):	$PE_{\text{total}} \leq 55 \text{ kWh}/(\text{m}^2\text{a})$




The duct distribution was via plenums and radial ductwork to each room.




11. Lüftungsplanung Kanalnetz



1 MVHR Detail 1:100



2 MVHR Detail 2 1:100



12. Wärmeversorgung

See section 11 – via air supply of Nilan unit with micro air source heat pump

13. Baukosten

14. Literatur

- [AkkP 5] Energiebilanz und Temperaturverhalten – mit Messergebnissen aus dem Passivhaus Darmstadt Kranichstein; Protokollband Nr. 5 des Arbeitskreises kostengünstige Passivhäuser, 1. Auflage, Passivhaus Institut, Darmstadt 1997
- [AkkP 13] Energiebilanzen mit dem Passivhaus Projektierungs Paket; Protokollband Nr. 13 des Arbeitskreises kostengünstige Passivhäuser, 1. Auflage, Passivhaus Institut, Darmstadt 1998
- [Ebel/Feist 1997] Witta Ebel und Wolfgang Feist: "Ergebnisse zum Stromverbrauch im Passivhaus Darmstadt Kranichstein" in "Stromsparen im Passivhaus"; Protokollband Nr. 7 zum Arbeitskreis Kostengünstige Passivhäuser; PHI; Darmstadt, 1997.
- [Feist 1988] Forschungsprojekt Passive Häuser; Projektziele - mit einem Kommentar des Autors zur 2. Auflage 1995, Institut Wohnen und Umwelt, Darmstadt, 1. Aufl. 1988, 2. Aufl. 1995
- [Feist 1993] Passivhäuser in Mitteleuropa; Dissertation, Universität Kassel, 1993
- [Feist/Werner 1994] Wolfgang Feist und Johannes Werner: "Gesamtenergiekennwert < 32 kWh/(m²a)"; Bundesbaublatt 2/1994
- [Feist 1997a] Wolfgang Feist, Tobias Loga: "Vergleich von Messung und Simulation" in "Energiebilanz und Temperaturverhalten"; [AkkP 5]; PHI; Darmstadt, Januar 1997.
- [Feist 1997b] Wolfgang Feist: "Der Härtestest: Passivhäuser im strengen Winter 1996/97"; GRE-Inform, 12/1997.
- [Feist 1997c] Wolfgang Feist: "Passivhaus Darmstadt Kranichstein - Planung, Bau, Ergebnisse", Fachinformation PHI 1997/4, 1. Auflage, 16 Seiten,
- [Feist 2000] Wolfgang Feist: "Erfahrungen objektiv: Messergebnisse aus bewohnten Passivhäusern"; in: Tagungsband zur 4. Passivhaus Tagung, Passivhaus Dienstleistung GmbH, 1. Auflage, Darmstadt 2000
- [PHPP 2007] Feist, W.; Pfluger, R.; Kaufmann, B.; Schnieders, J.; Kah, O.: Passivhaus Projektierungs Paket 2007, Passivhaus Institut Darmstadt, 2007
- [Rohrmann 1994] Bernd Rohrmann: "Sozialwissenschaftliche Evaluation des Passivhauses in Darmstadt"; Passivhaus-Bericht Nr. 11; Institut Wohnen und Umwelt; Darmstadt, September 1994.

15. PHPP-Ergebnisse

Passive House Verification



Building: Brook House
 Street: Hamlin Gardens
 Postcode/City: EX1 3BE Exeter
 Province/Country: Devon GB-United Kingdom/Br
 Building type: Residential Flats
 Climate data set: GB0005a-Exeter
 Climate zone: 4: Warm-temperate Altitude of location: 33 m

Home owner / Client: Exeter City Council
 Street: Paris Street
 Postcode/City: EX1 1JN Exeter
 Province/Country: Devon GB-United Kingdom/Br

Architecture: Gale and Snowden
 Street: Exeter Bank Chambers, 67 High Street
 Postcode/City: EX4 3DT Exeter
 Province/Country: Devon GB-United Kingdom/Br

Mechanical engineer: Gale and Snowden
 Street: Exeter Bank Chambers, 67 High Street
 Postcode/City: EX4 3DT Exeter
 Province/Country: Devon GB-United Kingdom/Br

Energy consultancy: Gale and Snowden
 Street: Exeter Bank Chambers, 67 High Street
 Postcode/City: EX4 3DT Exeter
 Province/Country: Devon GB-United Kingdom/Br

Certification: VARM: Low Energy Building Practice
 Street: 3 Admirals Hard
 Postcode/City: PL1 3RJ Plymouth
 Province/Country: Devon GB-United Kingdom/Br

Year of construction: 2024 Interior temperature winter [C]: 20.0 Interior temp. summer [C]: 25.0
 No. of dwelling units: 21 Internal heat gains (IHG) heating case [W/m²]: 2.9 IHG cooling case [W/m²]: 2.9
 No. of occupants: 35.2 Specific capacity [Wh/K per m² TFA]: 122 Mechanical cooling: x

Specific building characteristics with reference to the treated floor area

	Treated floor area m²	Value	Requirement	Alternative		Fulfilled?¹
				Criteria	criteria	
Space heating	Heating demand kWh/(m²a)	15	≤	15	-	yes
	Heating load W/m²	11	≤	-	10	yes
Space cooling	Cooling & dehum. demand kWh/(m²a)	1	≤	15	15	yes
	Cooling load W/m²	1	≤	-	11	yes
	Frequency of overheating (> 25 °C) %	-	≤	-	-	-
	Frequency of excessively high humidity (> 12 g/kg) %	0	≤	10	-	yes
Airtightness	Pressurization test result n ₅₀ 1/h	0.5	≤	0.6	-	yes
Non-renewable Primary Energy (PE)	PE demand kWh/(m²a)	124	≤	-	-	-
	PER demand kWh/(m²a)	49	≤	60	60	yes
Primary Energy Renewable (PER)	Generation of renewable energy (in relation to projected building footprint area) kWh/(m²a)	0	≥	-	-	yes

¹ Empty field: Data missing; '': No requirement

I confirm that the values given herein have been determined following the PHPP methodology and based on the characteristic values of the building. The PHPP calculations are attached to this verification. **Passive House Classic?** yes

Task: 2-Certifier First name: Michael Surname: Roe
 Certificate ID: 46333-46353_VARM_PH_20241219_MR Issued on: 23rd Dec 2024 City: Plymouth
 Signature: