

Project Documentation Gebäude-Dokumentation



Abstract / Zusammenfassung



38 Unit apartment building at Agar Grove, Camden, London

This report describes the main features of Agar Grove Block A, which is a new build 38 unit multifamily apartment building in the Borough of Camden in London.


1.1 Data of building / Gebäudedaten

Year of construction/ Baujahr	2017	Space heating / Heizwärmebedarf	13 kWh/(m²a)
U-value external wall/ U-Wert Außenwand	0.165 W/(m²K)		
U-value binstore soffit/ U-Wert Kellerdecke	0.187 W/(m²K)	Primary Energy Renewable (PER) / Erneuerbare Primärenergie (PER)	-- kWh/(m²a)
U-value roof/ U-Wert Dach	0.085 W/(m²K)	Generation of renewable energy / Erzeugung erneuerb. Energie	-- kWh/(m²a)
U-value window/ U-Wert Fenster	Uf-Fixed 1.020 W/(m²K) Uf-Opn 1.240 W/(m²K)	Non-renewable Primary Energy (PE) / Nicht erneuerbare Primärenergie (PE)	118 kWh/(m²a)
Heat recovery/ Wärmerückgewinnung	82 % (overall avg.)	Pressure test n ₅₀ / Drucktest n ₅₀	0.59 h-1

Special features/ Besonderheiten	Thermally broken steel walkway incorporating brick outer skin to South façade, thermally broken window cill detail & support for wide cavities, various thermally broken details, airtightness strategy, basalt wall ties resin anchored.
-------------------------------------	---

Brief Description


Agar Grove Block A (outlined in red) is a new build 38 unit multifamily apartment building in the Borough of Camden in London. It is the first phase of around 500 units masterplan for regeneration of a 1960s housing estate. It is one of the largest Passivhaus schemes in the UK currently. The council is the lead developer.




Overview of proposed Agar Grove Estate regeneration. ©Hawkins/Brown

The materials and building form of the masterplan were carefully developed by the architects to coordinate with and enhance the local neighbourhood, whilst also doubling the density of population. Approximately half of the masterplan is subsidised housing. The development is carefully phased over many years so that the residents can remain on site, moving only once; from their current into their new homes.

Block A, outlined in red above, faces North to the new estate and South to a busy railway line. The ground & first floor units are two level maisonettes, with 3-4 stories of apartments above. Most units are dual aspect.



01 North Elevation Unit Type Diagram



02 South Elevation Unit Type Diagram

Refuse Store	
Core	
Unit Type	Number
1B2P	12
2B3P	8
3B5P	11
3B6P	1
4B6P	6
Total =	38


Overview of Accommodation Schedule- Unit type breakdown in 3D

The budget was limited, the costs are comparable to a non-Passivhaus scheme.

The local vernacular informed the brick façade. This introduced design challenges to achieve low thermal bridging and costs.

Local regulations stipulated a district heating solution with a single large energy centre for the whole 500 unit masterplan. This was negotiated back to block-by-block communal heating which was designed, built and commissioned to demonstrate best-in-class efficiencies.

2 Responsible project participants

	Early stage	Post contract
Client	London Borough of Camden	London Borough of Camden
Architects	Hawkins\Brown	Architype
Main Contractor	-	Hill
Structural Engineer	Stantec	Stantec
Services Engineer & Building physics	Max Fordham	Robinson Associates
Passivhaus Planner	Max Fordham	Architype/Elemental Solutions
Landscape Architect	Grant Associates	Jo Wild
Project Manager & QS	Arcadis	
Certifying body	WARM	
Certification ID	6860	
Author of project documentation	Bertie Dixon & Robert White	
Date, Signature	29/03/2022  Robert White.	


3 Views of Agar Grove Block A



South Elevation ©Architype



North Elevation (North West) ©Architype



South Elevation – Typical Balcony View ©Hawkins/Brown



North Elevation (North East) ©Hawkins/Brown

4 Floor plans




Overview of Floor Plans

5 Sectional drawings



North East Cut Section from North to South via. BIM Model ©Architype



Longitudinal Cross Section from East - West




Cross Section from North - South

6 Elevation drawings



North Elevation



East Elevation



South Elevation



West Elevation

7 Construction details of the envelope and Passivhaus technology

7.1 Ground Floor & Bin Store Soffit

Ground Floor	75mm Concrete Screed, Vapour Control Layer, 135mm EPS Floor Insulation, 250mm Concrete Slab.	U-value 0.252 W/(m ² K)
Bin Store Soffit	65mm Concrete Screed, 10mm Acoustic Layer, 250mm Concrete Slab, 180mm Mineral Wool Soffit Insulation, 6mm Calcium Silicate Board.	U-value 0.187 W/(m ² K)

7.2 Construction including insulation of exterior walls Exterior wall assembly (s).

Exterior wall (a)	103mm Brickwork outer leaf, 150mm blown-in mineral wool insulation full filling cavity, thermally broken Basalt wall ties, 15mm airtight sand/lime/cement plaster, 200mm AAC Blockwork with thin joint mortar, 25mm acoustic glass fibre insulation, 15mm Plasterboard.	U-value 0.165 W/(m ² K)
Exterior wall (b)	25mm Brick slip system on 12.5mm cement carrier board affixed to thermally broken helping hand system, 80mm PIR insulation, 15mm airtight sand/lime/cement plaster, 200mm Reinforced Concrete, 25mm acoustic glass fibre insulation, 15mm Plasterboard.	U-value 0.230 W/(m ² K)

7.3 Construction including insulation of the roof


Roof build-up (s).

Main Roof	Extensive green roof substrate, filter fleece, drainage matt, torch-on modified bitumen cap sheet with integral root barrier & underlay membrane system torched on to a tapered PIR insulation system bonded to modified bitumen aluminium lined vapour control torched on to 250mm Reinforced Concrete roof deck, metal framed support system gypsum plasterboard.	0.085 W/(m²K)
Terrace Roof	Suspended decking system on torch-on modified bitumen cap sheet & underlay membrane system torched on to a tapered PIR insulation bonded to modified bitumen aluminium lined vapour control torched on to 250mm Reinforced Concrete roof deck, metal framed support system gypsum plasterboard.	0.085 W/(m²K)

7.4 Window data

Window	Triple low-e glazing filled with inert gas. Wooden window frames with insulated frame made of integrated polyurethane foam shells (CO2 foamed, CFC-free).	0.7 W/(m²K)
---------------	---	----------------

8 Description of the envelope



Overview of Airtightness boundary – View from North

The primary structure consists of a reinforced concrete frame erected as a cast in situ configuration. The main ground floor slab is laid in a raft configuration supported by reinforced concrete pile caps and associated piles. The base detail where the columns connect with the floor incorporate a thermal break integrated within the column's structure.



Overview Column base detail during construction

The columns support a primary floor slab on each floor which has been designed to have integral structural capacity and thickness to minimise the requirement for downstand beams within the construction of the intermediate floor slabs. The primary locations of down stands occurred within the party walls. This has an added

advantage, allowing for an unobstructed soffit surface to allow for the layout of various mechanical and electrical services from an early stage in the design.



Overview Column base detail during construction

The columns were designed in a 'blade' configuration. The column arrangement was optimised to ensure the narrow width fitted in line with the inner leaf of the cavity wall. This allowed for an uninterrupted internal finish.


The inner leaf of the cavity consists of a 200mm thick AAC lightweight blockwork laid using a thin joint mortar. The bottom starting course was set up using a standard mortar joint to take up any undulations in the concrete slab's surface.




Inner leaf of AAC lightweight blockwork

The airtightness line continues around the inner leaf wall (cavity side) by means of a 9-12mm sand/lime/cement parge coat layer which was trowel applied to the AAC blockwork- once the perimeter layer of parge compatible airtightness tape had been applied to the perimeter zones of the blockwork and insitu concrete structure.

The wall ties are a TeploTie, made from basalt fibres set in a resin matrix. The wall ties were set out in two rows whilst the outer leave of brickwork was being constructed. This ensured the vertical coursing was within construction tolerances. Pull-out test were carried out on the proposed strategy to verify it achieved the required structural design parameters. A specialist masonry drill bit was used to create a cone like cavity prior to inserting a selected structural resin and wall tie. The resin sealed around the parge coat ensuring the airtightness strategy was intact. An 'L' variation of the wall tie was used where the substrate is reinforced concrete around the stair cores, columns or shear walls.





Window & door structural openings are lined in a WBP plywood former which allowed for the accuracy and tolerances be achieved for the system selected. The plywood former allowed for the parge coat and associated airtightness taping to be applied around the plywood. This saved time in sequencing allowing the window installation follow on. Once the windows were fitted, an additional line of airtightness was applied to the window frame tagging back to the airtightness tape previously applied as part of the parge sequencing of works.



Image showing window closer installed


The cavity was fully filled with a specialist fire retardant mineral blown fibre insulation. In order to install the insulation a strategy was developed with the supplier to install false timber bricks with a predrilled hole which allowed for installation of the blown fibre once works to the external brick skin have been completed. Once insulation has been installed, the false timber bricks were replaced with the matching finish brick with mortar joints made good to match.

8.1 Windows & Rooflights/AOV

The windows for the project Windows are taken from Ideal Combi's Futura+ & Futura+ I range. The windows Tilt/Turn (in.) or Fixed. The main window frame is 149mm depth with a 48mm Sealed glass unit. The U value of the frames range between 1.02 W/(m²K) & 1.24 W/(m²K). The g-value ranges from 0.32 – 0.52 across orientations.

Glass make up	G value	Ug/Up value
48 mm Sandwich Panel		0,47
4-16-4-18-6,8 tough low e + float + lam low e	0,52	0,55
4-16-4-18-6,8 tough low e + float + lam low e	0,47	0,52
6,4-14-4 lam + tough low e	0,57	1,15
6,8-16-4-18-4 lam low e + float + low e	0,46	0,54
6,8-15-4-16-6,8 lam low e + float + lam low e	0,46	0,59
4-12-4-12-6,4 low e + float + lam low e KRYPTON	0,48	0,45
6-16-4-16-6,4 low e + float + lam low e	0,48	0,58
4-12-4-12-6,4 tough low e + float + lam low e KRYPTON	0,48	0,45
6,4-10-4-12-6,4 suncool 6633 lam + float + lam low e	0,33	0,50
6,4-16-4-16-6,4 suncool 6633 lam + float + lam low e	0,32	0,54
6,4-16-4-16-6,4 lam low e + float + lam low e	0,46	0,57
4-12-4-12-6,8 tough low e + float + lam low e KRYPTON	0,48	0,44
6-10-6-10-6 suncool 6633 tough + float + tough low e KRYPTON	0,33	0,53
6-10-4-12-6,8 suncool 6633 tough + float + lam low e KRYPTON	0,33	0,50

Typical glass G values and U Values

		Type: Futura+(48mm)ind Profil: PLU09-10L48
Fabrikant: Idealcombi A/S Tlf.: 96 88 25 00		
Type:	pur/alu	
Kildefil:	Se side 2	
Beskrivelse: Aluminium $\lambda = 160 \text{ W/m K}$ EPDM $\lambda = 0,25 \text{ W/m K}$ EPDM-foam $\lambda = 0,08 \text{ W/m K}$ IC PUR-1 $\lambda = 0,074 \text{ W/m K}$ PVC $\lambda = 0,17 \text{ W/m K}$ <i>Rude:</i> 4-18-4-18-4: $U_g = 0,62 \text{ W/m}^2 \text{ K}$ Kant 1: tps $\lambda_{\text{ekv}} = 0,4/0,25 \text{ W/m K}$		
Resultater: Dimension: (d·b) 149 mm x 60,0 mm U-værdi ramme/karm $U_f = 1,24 \text{ W/m}^2 \text{ K}$ <i>Kantkonstruktion:</i> Linjetab: Kant 1 (tps) $\Psi_{\text{tps}} = 0,037 \text{ W/m K}$		
Layout of tapered roof insulation system		

The window units are fixed into a plywood frame fixed within the window structural opening. This allowed the windows to be suspended into the cavity zone ensuring the maximum thermal performance is achieved. This allowed for the airtight taping to be applied to be windows and AAC blockwork prior to application of the sand/cement parge coat.




8.2 Roof Construction

The flat roof consists of a tapered insulation modified bitumen multi-layer roofing system.

The reinforced concrete structure was laid to zero falls. The VCL layer adhered to the primed concrete deck prior to installation of the 1:60 fall tapered PIR insulation system. The lowest thickness is 198mm rising to 378mm at its highest point. The Insulation is finished with a self-adhesive underlay and a torched on final cap sheet. The final cap sheet was suitable to receive the brown/extensive roof system with its root resistance properties.



The average U value of the flat roof is 0.09 W/m²K.

All drainage falls towards a linear gutter sump along south orientation of the building. A series of outlets are positioned above the parapet Halfen thermal breaks. The outlets drain into a linear gutter positioned the length of the façade onto the finished brickwork. All drainage down pipes are external and coupled at each balcony level draining into the main drainage system.



The parapets are thermally separated using a propriety Halfen thermal break system which is 120mm thick. The primary Halfen modules which form part of the structural integrity of the parapet are set out in accordance with the system structural design requirements. The modules are designed to take the parapet loads with the reinforcement linking with the spaced modules.

As shown in the extract below, the intermittent structural elements (shown blue) are infilled with unconnected sections (shown red) of the system ensuring the most efficient thermally broken solution.

[illegible]

Technical drawing of a rectangular structure, likely a component of a building or industrial facility. The drawing shows a plan view with dimensions: 180 (width), 1975 (length), 125 (width of a small rectangular section), and 200 (width of a larger rectangular section). The drawing includes a small rectangular section at the top left, a larger rectangular section at the bottom left, and a long rectangular section extending to the right. The dimensions are indicated by lines and numbers.

Technical drawing of a door frame assembly. The drawing shows a cross-section of the frame with dimensions: 180 (width of the top part), 270 (height of the top part), 125 (height of the middle part), 130 (height of the bottom part), and 325 (total height). A blue shaded area is present in the middle part of the frame.




Image showing Halfen Thermal Breaks at parapet and adjoining junctions


8.3 Special features

Many of the expressed architectural features required innovative use of specialist thermal breaks. Some examples have been provided below.

The main entrance and maisonette canopies along the North façade utilise a series of intermittent connections between the concrete and the steel frame which carries the stone finish to the canopies. An example of the configuration used can be seen below.



Juliet balconies along the North façade utilised a similar thermally broken solution.



The screened balconies on the South façade are of steel construction tied back to the primary structure using point fixed thermal breaks back to the primary reinforced concrete structure. The inner line of the steel structure supports the brick façade infilled to each bay to complete the external finish.






Image showing South East corner balcony detail.

9 Planning of ventilation ductwork

9.1 Maisonettes


- Each Maisonette is vented by a single ComfoAir Q350 MVHR unit, located in the hall cupboard adjacent to the external wall. Air is drawn directly from outside.
- No pre or post heater was fitted to the ventilation.
- Ducting is spiral wound galvanised circular ducts above a false ceiling.
- Effective heat recovery 81%
- Specific input power 0.42 Wh/m³
- Typical external pressure to atmosphere 10 Pa
- Typical external pressure to building 15 Pa



PA-00-03		BASIC 100 (m³/h)
EXTRACT	STANDARD (m³/h)	MAXIMUM (m³/h)
KITCHEN / DINING	68	115
BATHROOM	35	59
UTILITY STORE	15	25
WC	24	41
TOTAL	142	240
SUPPLY		
LIVING ROOM	44	74
BEDROOM 00-03-09	32	54
BEDROOM 00-03-10	32	54
BEDROOM 00-03-12	17	29
BEDROOM 00-03-13	17	29
TOTAL	142	240
Typical Maisonette ventilation rates.		


9.2 Apartments

- The apartments are vented by two roof-mounted Swegon Gold RX AHUs, one AHU per riser. These include a rotary heat exchanger, and no pre- or post-heating.
- The supply & extract ducts are routed via vertical risers; one riser stack of apartments, there are 14no risers in total. Branches to each apartment have flow rate modulation & control by Swegon Adapt motorised dampers with Swegon Wise control. In this way the resident can control the ventilation rate of their apartment. Acoustic and fire separation required for each branch.
- Effective heat recovery 82%
- Specific input power 0.45 Wh/m³
- Typical external pressure to atmosphere 0 Pa
- Typical external pressure to building in design 101Pa; measured at commissioning 115Pa (favourably compares to typical VAV system pressures of 400Pa)



PA-03-03		BASIC 65 (m³/h)
EXTRACT	STANDARD (m³/h)	MAXIMUM (m³/h)
KITCHEN	46	60
BATHROOM	31	40
UTILITY STORE	15	20
TOTAL	92	120
SUPPLY		
LIVING / DINING ROOM	37	48
BEDROOM 03-03-04	35	46
BEDROOM 03-03-05	20	26
TOTAL	92	120


Typical apartment ventilation rates




Ducting during installation



Ventilation riser, branch to apartment and damper arrangement.



Screen shot of Swegon AHU controller



Communal AHU on roof.

10 Heat supply

10.1 Communal heating design & commissioning approach

The planning department stipulated a district heating system, with a single large energy centre for the whole 500 unit masterplan. The designers presented to the department the technical and financial issues with this policy. These include:

- Inefficiencies due to sizing & modulation of systems during 10+ years of masterplan phasing,
- Required higher temperatures and pressures,
- High capital and running costs
- Risk of summer overheating

The negotiated compromise was a block-by-block communal heating system, with a plant room for each building containing gas boilers. Primary low temperature hot water (LTHW) is circulated to a heat interface, metering and control unit (HIU) in each apartment.

The efficiency of these systems is limited by their extremely extended geometry; heat is circulated 24/7 all year through kilometres of pipework. The heat losses from such systems can be reduced through good design, but a certain amount is unavoidable. This presented the designers with a challenge to achieve PER rates and avoid summer overheating. These issues are often not considered fully in communally heated non-Passivhaus developments, as described elsewhere¹

The design approach was:

- To limit heat loss by minimising pipe length, diameter, and flow temperatures. The insulation is high quality of specification and installation. The HIUs are very well insulated SAV units.
- The return temperature must be as low as possible to reduce heat losses & improve boiler condensation & thus efficiency. Avoiding hot water storage in the flats in favour of large capacity heat exchangers provides low return temperatures.
- The space heating is fed directly (as opposed to indirectly via a heat exchanger). The circulating flow rate is variable according to demand, controlled by a differential pressure sensor.

A good design is only half of the solution; the installation was very carefully completed by the skilled team, and the commissioning process was a significant enhancement on normal procedures. Once the system was fully commissioned and set to work, the system was 'road tested' over 48 hours. Typical demands for heating and hot water were simulated on site by running heating and opening water outlets. The heat metering system was fully operational and recording data during this test.

The heat losses and return temperatures were logged and compared to benchmarks. The benchmarks build upon the excellent work of Fairheat² in this area. This measurement highlighted numerous issues with the boiler set up and various valve settings around the building. Only once the benchmarks were achieved was the system

¹ New Metrics for Communal Heating Design - Max Fordham

² <https://fairheat.com/>

accepted as completed. This level of commissioning is very unusual. It gave the contractor and client teams reassurance that the system was fully compliant, before it was handed over.

The metrics against which the performance was measured.

- <90W per customer continuous distribution loss between plant room and HIU; (<50W is often achieved nowadays). *Measured value in commissioning for Block A; 94W³*
- <30m total distribution pipe length, per customer;
- <38kW HIU rating for a 1 bathroom property; demand calculated on the Danish, or preferably, the Swedish Curve (e.g. total heat load >3kW per apartment for schemes >60 units);
- V_{WART}<40C; i.e. the Volume Weighted Average Return-water Temperature, which can be calculated with relative ease from metering data over a period, say 24 hours; *Measured value in monitoring for Block A; 35-40C.*
- Bypass flow < 5% i.e. flow that is unaccounted for by the HIUs.

These values can be compared to any communal heated project at any stage: during feasibility, design, commissioning and ongoing performance monitoring.

The design features and commission process are described in detail in the article 'New metrics for communal heating'⁴. Many of the approaches have since been included in national best practice technical guidance⁵

At Agar Grove the communal heating was tested during commissioning using these metrics; in order to demonstrate actual in-use performance prior to handover. This is an example of an as-built yet pre-handover quality assurance check. Although this is rarely implemented, the author feels strongly that this type of testing is of critical importance to delivering quality for large bespoke systems such as communal or district heating.

10.2 Communal system arrangement

A plant room on the roof level contains 4no boilers. By selecting multiple small boilers, this allows modulation down to meet the very small heat demand (pipe heat loss only- this load is experienced around 70% of the year). The pumps are variable speed with a remote pressure sensor; to ensure minimum pumping power and lowest return water temperatures.

Each pair of apartments is served by one riser: there are 6no heating risers. When compared to a more-typical single riser with long horizontal branches, very little horizontal pipework is required. This reduces the total length of pipework substantially. Separately located are two risers for mains water, which can thus remain cool. Pipe work is sized at higher pressure loss to reduce bore & so heat loss. High quality insulation including thermally broken supports is applied to the full length of circulating pipework, including all fittings and components, and throughout all wall/floor penetrations.

10.3 Apartment & maisonette heating

³ <https://www.cibsejournal.com/case-studies/agar-grove-performance-assured/>

⁴ New Metrics for Communal Heating Design - Max Fordham

⁵ <https://www.cibse.org/knowledge/knowledge-items/detail?id=a0q3Y00000IMrmGQAT>

Low temperature hot water (LTHW) at 55-65C is circulated to a heat interface, metering and control unit (HIU) in each apartment. Fully insulated SAV 5 HIUs were selected for their minimum heat loss and reliable controls. Hot water is generated instantaneously & hygienically on demand by a heat exchanger. Hot water distribution is in a radial arrangement with 10mm small bore pipework to reduce dead leg volumes.

The apartment space heating is connected directly to the communal LTHW system (as opposed to indirectly via a second heat exchanger). Radiators are generously sized. They are thermostatically controlled with flow limiting valves. All of these features ensure low return temperatures, even at part loads. Only two radiators were required per apartment to provide the necessary heat. In the bathrooms 'wet' towel rails connected to the heating circuits are provided. These also have an electric element for summer use. If residents require a very warm interior, portable electric radiators are available for their use.



Thermally isolated pipe supports, during installation.




4no boilers allow fine modulation for low heat loads. Circulator pumps were also selected and arranged to modulate to <5% of peak



Remote differential pressure sensor for close control of variable speed LTHW pumping.


11 PHPP calculations

Passive House Verification									
				Building: Flats 1 - 38 Street: 14 - 16 Wrotham Road Postcode/City: NW1 0RE London Province/Country: GB-United Kingdom/Britain Building type: Domestic Climate data set: GB0001a-London (Central) Climate zone: 4: Warm-temperate Altitude of location: 33 m					
				Home owner / Client: London Borough of Camden Street: 33-35 Jamestown Road Postcode/City: NW1 7DB London Province/Country: GB-United Kingdom/Britain					
				Mechanical system: Max Fordham / Mark Robinson Street: 42-43 Gloucester Crescent / Unit 1, 6 Enterprise Way Postcode/City: NW1 7PE / SW London Province/Country: GB-United Kingdom/Britain					
				Certification: WARM: Low Energy Building Practice Street: 3 Admirals Hard Postcode/City: PL1 3RJ Plymouth Province/Country: Devon GB-United Kingdom/Britain					
Architecture: Hawkins Brown / Architype Street: 159 Saint John Street / Upper Twyford Postcode/City: EC1V 4QJ / HR London / Hereford Province/Country: London / Herefordshire GB-United Kingdom/Britain				Energy consultancy: Max Fordham / Architype Street: 42-43 Gloucester Crescent / Upper Twyford Postcode/City: NW1 7PE / HR London / Hereford Province/Country: London / Herefordshire GB-United Kingdom/Britain					
Year of construction: 2018 No. of dwelling units: 38 No. of occupants: 81.3				Interior temperature winter [°C]: 20.0 Interior temp. summer [°C]: 25.0 Internal heat gains (IHG) heating case [W/m²]: 2.7 IHG cooling case [W/m²]: 3.6 Specific capacity [Wh/K per m² TFA]: 84 Mechanical cooling:					
Specific building characteristics with reference to the treated floor area									
		Treated floor area m²	3265.0		Criteria		Alternative criteria	Fulfilled? ²	
Space heating	Heating demand kWh/(m²a)	13	≤	15	-			yes	
	Heating load W/m²	9	≤	-	10				
	Frequency of overheating (> 25 °C) %	6	≤	10			yes		
	Frequency excessively high humidity (> 12 g/kg) %	0	≤	20			yes		
Airtightness	Pressurization test result n ₅₀ 1/h	0.6	≤	0.6			yes		
Non-renewable Primary Energy (PE)	PE demand kWh/(m²a)	118	≤	120			yes		
<small>² Empty field: Data missing; "-": No requirement</small>									
I confirm that the values given herein have been determined following the PHPP methodology and based on the characteristic values of the building. The PHPP calculations are attached to this verification.								Passive House Classic? yes	

Snapshot of Verification Overview

The building achieved a final Heating Demand of 13.48 kWh/(m²a) which is less than the Passivhaus criteria of 15 kWh/(m²a). Although the building was certified under the Heating Demand criteria, the building also achieved a favourable Heating Load value of 9.36 W/m² which is less than the alternative certification criterion of 10 W/m².

Frequency of overheating (>25°C) calculates at 6% which passes based on the Passivhaus maximum criteria of 10%. Individual units have been assessed using dynamic thermal simulation methodology and each unit passes based on the individual unit cooling/ventilation strategy agreed for the design.



Heating Energy Balance (Monthly)

The transparent (windows & doors) elements account for just over a third, 33.8% of the total losses, the external walls account for almost a fifth, 15.7%.

The transparent elements account for 43.7% of total heat gains Internal heat sources contribute around a third, 33.3%. Resulting in the heating demand that remains at 13.48 kWh/(m²a).

12 Construction costs

- The Project was delivered by Camden Council's Community Investment Programme (CIP) which invests in the long term future of the borough.
- The clients quantity surveyors describe the build costs were £2,713 /m² as per the build contract, which was comparable to a Non-Passivhaus scheme on this site.

13 Measured results in use

13.1 Measurement data acquisition

Max Fordham and LB Camden performed post occupancy evaluation. This involved:

- Monitoring of internal conditions
- Monitoring of building services set points and efficiencies
- Interviews with occupants to gauge their comfort & satisfaction, as part of regular Building User Surveys.

13.2 Measured energy consumption values; communal heating

As described above, the communal heating system was thoroughly tested against robust metrics post-completion yet pre-handover. This included 24 hours of running in 'idle' then 24 hours of mimicked actual demand.

Basic quality control checks such as this are unfortunately a rarity, even in high profile buildings such as this. The PHI do not explicitly require validation of communal system distribution efficiency prior to certification. This is a weakness in the process, as highlighted in a paper presented to the PH Conference in Munich, 2018⁶.


The results of the as built testing of the communal heating systems at Agar Grove are presented below. These metrics can be set at the briefing stage, checked at each design stage, measured pre-handover and in occupation.

6

<https://www.maxfordham.com/assets/media/downloads/20180310%20Efficient%20heat%20system%20design%20in%20large%20PassivHaus%20multifamily%20buildings;%20A%20UK%20experience.pdf>

KPI		Target Value	London scheme measured
Total distribution pipe length per customer	m/ customer	30	25
VWART Volume Weighted Average Return-water Temperature	°C	<40	40
Bypass flow	% of peak	<5	0
Continuous distribution loss between plant room and HIU	W/ customer	50	90

Communal heating scheme; measured performance at commissioning vs. best-case target metrics⁷



Instantaneous peak heating load was measured as 57kW in 2018. This is approximately 17W/m². This is heat load as measured at the boiler, so will include losses from distribution, which may partially explain the increase from PHPP heat load

⁷ <https://www.maxfordham.com/research-innovation/new-metrics-for-communal-heating-design/>


(measured in occupied zone) or 9W/m². External & internal conditions, hot water load and controls may also contribute to the differential between prediction and measurement.

At design stage Agar Grove communal system was designed at 55C flow and 35C return. The low flow temperature was set to minimise distribution losses. The flow temperature has been increased in occupation by facilities management to 65C flow 35C return. This was a response to improve stability of the heat supply.

Distribution losses in use have been reported as 162W/customer. If this figure is too high it can lead to summer overheating amongst other issues. This sensitivity is relevant to any modern efficient multifamily building.

Although this is an increase on the target, it still compares very favourably to other measured schemes. Typical modern systems are at 400W, and national averages are above 700 W/customer⁸.

A good measurement of the health of a communal heating system is the delta or difference between flow and return temperatures. Communal systems may typically be designed at 80C flow, 60C return (20K delta). However, in reality, due to poor design or commissioning they will operate at less than 5K delta. This leads to high heat losses and pumping power.



⁸ <https://www.gov.uk/government/publications/energy-trends-march-2018-special-feature-article-experimental-statistics-on-heat-networks>

The graph above, of May to August 2019, shows a stable differential of around 30K. This demonstrates a well-designed, installed, commissioned, and maintained system.

13.3 Ventilation monitoring

The communal ventilation systems are equipped with onboard monitoring systems. At the time of writing results from this are not available for review.

13.4 The user experience; in-use surveys

The redevelopment of the wider Agar Grove Estate is deliberately phased over 10+ years; in order to minimise the disruption to the social fabric of the existing community. The phasing includes a single decant for all but one. The decant strategy has been carefully planned to allow for the single decant and redeveloping in stages across six phases. This fundamental principle was set by LB Camden to minimise disruption to residents.

Building User Surveys were undertaken in the first year by LB Camden. Most homes responded; the results were broadly positive. Some quotes and results presented below.

- “Light, airy and comfortable.”
- “Never feel the cold in this flat”
- “Quietness, light, space”
- Air quality is good or very good (86% agree)

The survey identified a need to remind users to operate internal curtains to control solar gain.


Condition monitoring of a few example apartments was carried out for one calendar year. CO₂, relative humidity and internal temperature were logged at half hour intervals.

- The CO₂ levels were found to be rarely above 600ppm with occasional maximums of 1000ppm.
- Relative humidity was found to be between 60%- 30% with occasional lows of 25%
- Winter internal temperature did not drop beneath 20C
- Summer internal temperature was above 26C in June & July. Fewer than 10 days in the year were greater than 30C. The summer in question was declared by the Met Office declared to be the joint hottest on record⁹.

⁹ https://en.wikipedia.org/wiki/2018_British_Isles_heat_wave

13.5 Measured energy demand in Agar Grove

The results of metered energy demand are presented below.




Specific energy value (final energy)	Energy source	Measured data 2018/19
All heat ¹⁰	Gas via communal system	44 kWh/m².a
All electricity ¹¹	Grid	20 kWh/m².a

Measured total energy consumption from 2018/19 shows the building total energy consumption is within Passivhaus metrics.

¹⁰ Including distribution losses, excluding boiler efficiency

¹¹ Total metered electrical use within flats (excluding communal systems) .



Winter sun penetrating through the balconies deep into the South facing living rooms

14 References

See footnotes in body text.

15 News Articles

Awards:

- Passivhaus Trust Award 2021; Large Building Category winner
- CIBSE Building Performance Awards 2020; Residential project of the year
- New London Architecture 2019 Overall winner
- New London Architecture 2019 Sustainability prize
- CIBSE Awards 2020 - Project of the Year - Residential - Winner
- Housing Design Awards 2019 - Completed - Shortlisted
- RTPI Awards 2019 - Excellence in Planning for Homes (small) - Shortlisted
- London Planning Awards 2019 - The Mayor's Award for Sustainable and Environmental Planning, and Good Growth - Winner
- The Sunday Times British Homes Awards 2018 - Development of the year (more than 100 homes) - Shortlisted
- The Sunday Times British Homes Awards 2015 - Housing Project - Commendation
- Housing Design Awards 2015 - Project Schemes - Winner
- BD Architect of the Year Awards 2014 - Masterplanning & Public Realm - Shortlisted
- BD Architect of the Year Awards 2013 - Masterplanning and Public Realm - Shortlisted

Articles:

- <https://www.cibsejournal.com/case-studies/agar-grove-performance-assured/>
- <https://www.cibsejournal.com/case-studies/london-calling-passivhaus-goes-mainstream-in-camden/>
- <https://www.maxfordham.com/research-innovation/new-metrics-for-communal-heating-design/>
- <https://passivehouseplus.ie/magazine/new-build/big-time-uk-s-largest-passive-scheme-comes-to-camden>
- <https://www.cibse.org/Building-Performance-Awards/2020-Winners/Project-of-the-Year-%E2%80%93-Residential>