Project Documentation Gebäude-Dokumentation



1 Abstract / Zusammenfassung



'Geanaisean' Private Home, Strathpeffer, Scottish Highlands

1.1 Data of building / Gebäudedaten

Year of construction/ Baujahr	2019	Space heating /	15 kWh/(m²a)				
U-value external wall/ U-Wert Außenwand	0.102 W/(m ² K)	Heizwärmebedarf					
U-value floor slab U-Wert Kellerdecke	0.071 W/(m²K)	Primary Energy Renewable (PER) / Erneuerbare Primärenergie (PER)	145 kWh/(m²a)				
U-value roof/ U-Wert Dach	0.101 W/(m ² K)	Generation of renewable energy / Erzeugung erneuerb. Energie	69 kWh/(m²a)				
U-value window/ U-Wert Fenster	0.86 W/(m ² K)	Non-renewable Primary Energy (PE) / Nicht erneuerbare Primärenergie (PE)	62 kWh/(m²a)				
Heat recovery/ Wärmerückgewinnung	90.3 %	Pressure test n _{50 /} Drucktest n ₅₀	0.34 h-1				
Special features/ Besonderheiten	Solar thermal hot water panels, PV panels, electric car charging point, rainwater harvesting system						

1.2 Brief Description

Geanaisean Passive House, Strathpeffer, Highlands

'Geanaisean' is a certified Passivhaus situated in the village of Strathpeffer in the Scottish Highlands at an altitude of 105m above sea level.

The house is built in the garden ground of a former bungalow, which was derelict beyond repair. The site has good solar access to the south side, and is partially shaded by native woodland to the east and north-east.

The house was built using locally-grown untreated timber in an off-site panelised process which enabled the building to be erected within days on site using a crane. The off-site process allowed careful air-tightness detailing to happen in a dry, warm factory setting, leaving fewer junctions to be dealt with on site.

Insulation is by way of blown cellulose and woodfibre – demonstrating a fully vapour-open construction system, which is beneficial to the internal environmental quality for the occupant, as well as to the planet. Use if membranes was avoided as far as possible, with OSB board utilised as the air-tightness layer, taped at junctions.

The client was aware of the Passivhaus standard, and understood its benefits from the start. In addition, renewables were used to further reduce energy impact of the building and its reliance on the grid.

1.3 Responsible project participants / Verantwortliche Projektbeteiligte

Architect/ Entwurfsverfasser	Catriona Kinghorn, for MAKAR Ltd https://makar.co.uk/	
Implementation planning/ Ausführungsplanung	Catriona Kinghorn for MAKAR Lyd. https://makar.co.uk/	
Building systems/ Haustechnik	Catriona Kinghorn, MAKAR Ltd. https://makar.co.uk/	
Structural engineering/ Baustatik Building physics/ Bauphysik	SF Structures https://www.sfstructures.com/ Catriona Kinghorn, MAKAR Ltd. https://makar.co.uk/	
Passive House project planning/ Passivhaus-Projektierung	Catriona Kinghorn, MAKAR Ltd. https://makar.co.uk/	
Construction management/ Bauleitung	MAKAR Ltd. https://makar.co.uk/	
Certifying body/ Zertifizierungsstelle Certification ID/ Zertifizierungs ID	Passivhusbyrån Ingo Theoboldt http://www.passivhusbyran.se/ Project-ID (www.passivehouse-database.org) Projekt-ID (www.passivehouse-database .org)	6865

Author of project documentation / Verfasser der Gebäude-Dokumentation Catriona Kinghorn

Date, Signature/ Datum, Unterschrift

2 Photographs



South Elevation




East and North Elevations

Project Documentation




Typical internal view - from kitchen to living space on left and dining space on right

3 Section Drawing



Two Cross Sections (dimensioned)

4 Floor Plans



Floor Plans (dimensioned)

5 5.1 Floor Slab

Hardwood floor finish on 45 mm battened service zone, on 125 mm reinforced concrete slab, on slip membrane, on 300 mm Quinn Therm ground floor insulation, on 1200 g DPM, on 150 mm sand blinded hardcore. Perimeter load bearing Thermalite Aircrete Trenchblock insulated externally with NBT plinth board. U-value: 0.071 W/m2k



Under-slab insulation during construction.

5.2 Exterior Walls

150x25 mm vertical board-on-board heartwood larch cladding on 38x50 mm horizontal battens, on 25x50 mm vertical battens, on prefabricated wall panel comprising: 180 mm Pavatex Isolair insulation board on C16 kiln-dried regularised untreated 245 mm studs with cellulose insulation, with 18 mm OSB 3 internal lining board as airtight layer taped at all junctions. Internally there is a 45 mm battened service zone insulated with Pavaflex wood fibre insulation, finished with 12.5 mm plasterboard, taped and filled. Uvalue: 0.091 W/m2k



Wall panel during factory construction with all cavities filled with Warmcel cellulose insulation (Panel uncovered for photograph, typically Warmcel pumped to a density of 65kg/m³ to meet requirements for off-site transportation).

5.3 Roof

Anthracite grey big six profile metal roofing on 50x50 mm battens, on 120x50 mm Douglas fir secondary rafters screwed to prefabricated roof panel comprising: Roofshield membrane on 180 mm Isolair wood fibre insulation, on 245 mm C16 kiln-dried regularised untreated rafters with cellulose insulation, lined internally with 18 mm OSB 3 airtight layer, all junctions taped. 45 mm internal service zone insulated with Pavaflex wood-fibre batts. 12.5 mm plasterboard internally, taped and filled. U-value: 0.090 W/m2k



Roof during construction

5.4 Windows and Doors


Internorm HF310 aluminium/timber composite triple glazed windows. Average installed U value average: 0.80 W/m2k

Windows and doors installed in panels in the off-site factory, with OSB panelled ingoes, taped at all junctions to create an airtight opening. Taped junction to all 4 sides of the window frame completes the air-tight installation. Externally the woodfibre board covers the front face of the frame, completing the thermal envelope. Detail section shown on following pages.


$$\label{eq:Frame} \begin{split} & \underline{Frame} \\ & Uf: 0.86 \ W/m^2 K \\ & Frame \ width: 0.780 \ m \\ & Glazing \ edge \ thermal \ bridge: 0.036 \ W/m K \\ & Installation \ \Psi \ 0.020 \ - \ 0.036 \ W/m K \\ & \underline{Glazing} \\ & Type: \ Internorm \ 33U \ Iso \ Solar X Plus \\ & g-Value: \ 0.59 \\ & Ug: \ 0.54 \ W/m^2 K \end{split}$$



Internal view of Internorm door and sidelight.



 $Psi(top,A,rev.) = 0.020 W/(m \cdot K)$



18/09/2018 D./PassivhusbyråniMakar - Dawson House\TB/iMindow_cill_optionA_20180910_fRsi.ftx

fixo pro 7.0.633.1

Windows top and cill therm model

2

Rooflights

Fakro FTT U8 Thermo triple glazed roof windows. Average installed U-value: 0.94 W/m2k


Rooflights installed in a similar way to the windows – with airtight taped installation internally and insulated Fakro flashing completing the external thermal envelope.

<u>Frame</u>

Uf: 1.08-1.10 W/m²K Frame width: 0.092 – 0.112 m Glazing edge thermal bridge: 0.034 – 0.037 W/mK Installation Ψ 0.040-0.050 W/mK <u>Glazing</u> Type: Fakro Quadruple g-Value: 0.55 Ug: 0.51 W/m²K



Internal view of Fakro rooflights



Details through typical cross section


6 Air-tight envelope

The air-tight envelope is formed on the inside face of the timber kit using 18mm OSB , taped at all junctions to the walls and roof. The concrete slab forms the floor air-tight layer. Specialist SIGA tape junctions the OSB walls to concrete floor slab. All openings are taped including windows, doors, supply and exhaust vents, and any through-the-floor drains.

The house was air tested mid-build, once the OSB envelope was complete but prior to battening for services or installing dry lining board. Minor leaks found at this time were sealed in order to achieve <0.4ach. At completion the air-tightness test achieved 0.34ach. All air tests were carried out by Jamie Reid, director of Air Tight Build. The section below shows the air-tight layer and key junctions.



Air-tightness envelope in plan and section




Extract from air-tightness test report



Taping to junctions of OSB and windows at first floor

7 7.1 Ventilation ductwork

The exhaust and intake through-the-wall vents are located on the north facing external wall. The eaves space on the north side is utilised to move the internal MVHR ductwork east and west, with the service zone in the roof, and the depth of the intermediate floor to move the ducts north and south – all inside of the air-tight and insulated envelope.





Extract from ventilation system design pack

7.2 Central Unit

The ventilation unit is a Paul Novus 300 with an effective heat recovery efficiency of 90.3%. Specific efficiency is 0.24 Wh/m³



Verner stove in living room, with Paul MVHR unit visible in plant cupboard in background.

8 Heat supply system

Space heating is provided by way of a wood burning stove, which feeds a back boiler and large thermal store. Solar thermal panels contribute to the thermal store, and PV panels automatically feed the electric immersion.

Two radiators are fed from this system, one on each floor.



Radiator in living space – which provide heat from the thermal store when the wood burner is not being used.

Passive House Verification

and the second	Building: GEANAISEAN								
			Street:	GOLF COURSE ROAD					
				Postcode/City:	IV14 9AS	14 9AS STRATHPEFFER			
			Province/Country:	HIGHLAND	UK				
			Building type:	NEW RESIDENTIAL HOUSE					
		and the state of the second	A REAL PROPERTY OF THE PARTY OF	Climate data set:	GB0018a-Av	riemore			
				Climate zone:	Climate zone: 3: Cool-temperate Altitude of location: 105 m Home owner / Client: TIM DAWSON				
				Home owner / Client:					
the second se				Street:	GOLF COURSE ROAD				
and a second				Postcode/City:	IV14 9AS STRATHPEFFER				
			Province/Country:	HIGHLAND UK					
Architecture:	Architecture: CATRIONA KINGHORN FOR MAKAR LTD			Mechanical system:	AIR CHANGE LTD				
	CLACHANDREGGY, DORES ROAD					ONS BUSINESS	CENTRE, KINT	AIL HOUSE	
Postcode/City:	IV2 6DJ			Postcode/City:		1	BUSINESS PAP		
Province/Country:	HIGHLAND	ик		Province/Country:			UK		
Energy consultancy:	9				INGO THEO	BOLDT			
Street:						N MILL PLACE			
Postcode/City:				Postcode/City:		EDINBURGH			
Province/Country:				Province/Country:		and the second second second second	UK		
		1		,		1			
Year of construction:	2019			r temperature winter [°C]:	20.0	-	p. summer [°C]:	25.0	
No. of dwelling units: No. of occupants:	1 2.8	Ir	- /	HG) heating case [W/m ²]: acity [Wh/K per m ² TFA]:	2.5 84		ing case [W/m²]: chanical cooling:	2.9	
No. of occupants:	2.8		Specific cap	acity [wh/k per mª TFA]:	84	Med	chanical cooling.		
Specific building char	acteristics wit	h reference to the treated fl	oor area						
	т		105.0			Alternative			
		reated floor area m ²	135.8	1	Criteria	criteria	1	Fullfilled? ²	
Space heating		Heating demand kWh/(m²a)	15	≤	15	-		ves	
		Heating load W/m ²	12	≤	-	10		,	
Space cooling	Coolina &	dəhum. dəmand kWh/(m²a)	_	5	-				
Cooling load W/m ²			5				-		
F	<i>(</i>)	-			40		1		
		neating (> 25 °C) %	0	≤	10			yes	
Frequency exces	sively high hun	nidity (> 12 g/kg) %	0	≤	20			yes	
Airtightness	Pressurizati	on test result n ₅₀ 1/h	0.4	≤	0.6			yes	
Non-renewable Prima	ry Energy (PE)	PE demand kWh/(m²a)	62	≤	120		ſ	yes	
						1	1		
2.5.7		PEB demand kWb//m2a	145	<		1 .			
Primary Energy Renewable (RER)	Generat	PER demand kWh/(m²a) ion of renewable	145	5	-	-		-	
Primary Energy Renewable (PER)	Generat	PER demand kWh/(m²a) ion of renewable energy kWh/(m²a)	145 69	≤ ≥	-	-		-	
	Generat	ion of renewable			-	- - 2 ² En	npty field: Data missi	- ng;'-':Norequirement	
Renewable (PER)		ion of renewable energy kWh/(m²a)	69	2	- -			- ng;'-∵No requirement	
Renewable (PER)	s given herein h	ion of renewable energy kWh/(m²a) nave been determined followi	69 ng the PHPP metho	2	- - characteristic		npty field: Data missi ouse Classic?	- ng; '-': No requirement yes	
Renewable (PER)	s given herein h	ion of renewable energy kWh/(m²a) have been determined followi lations are attached to this v First name	69 ng the PHPP metho rerification.	2 dology and based on the d	- - characteristic Surname	Passive H			
Renewable (PER)	s given herein h	ion of renewable energy www.www.com wave been determined followi ulations are attached to this v	69 ng the PHPP metho erification.	2	Sumame	Passive H		yes	
Renewable (PER)	s given herein h	ion of renewable energy kWh/(m²a) have been determined followi lations are attached to this v First name	69 ng the PHPP metho erification. 9: Issued on:	≥ dology and based on the o		Passive H		yes	
Renewable (PER)	s given herein h	ion of renewable energy kWh/(m²a) have been determined followi lations are attached to this v First name	69 ng the PHPP metho erification. 9: Issued on:	2 dology and based on the d	Sumame	Passive H		yes	
Renewable (PER)	s given herein h	ion of renewable energy kWh/(m²a) have been determined followi lations are attached to this v First name	69 ng the PHPP metho erification. 9: Issued on:	≥ dology and based on the o	Sumame	Passive H		yes	
Renewable (PER)	s given herein h	ion of renewable energy kWh/(m²a) have been determined followi lations are attached to this v First name	69 ng the PHPP metho erification. 9: Issued on:	≥ dology and based on the o	Sumame	Passive H		yes	
Renewable (PER)	s given herein h	ion of renewable energy kWh/(m²a) have been determined followi lations are attached to this v First name	69 ng the PHPP metho erification. 9: Issued on:	≥ dology and based on the o	Sumame	Passive H		yes	
Renewable (PER)	s given herein h	ion of renewable energy kWh/(m²a) have been determined followi lations are attached to this v First name	69 ng the PHPP metho erification. 9: Issued on:	≥ dology and based on the o	Sumame	Passive H		yes	
Renewable (PER)	s given herein h	ion of renewable energy kWh/(m²a) have been determined followi lations are attached to this v First name	69 ng the PHPP metho erification. 9: Issued on:	≥ dology and based on the o	Sumame	Passive H		yes	

PHPP, Verification

Geanaisean PHPP Final.xlsx

10 10.1 Construction costs

£365,000 'turn-key' construction cost including design fees.

10.2 Building costs

The house is largely powered by PV, and heat is provided by burning wood logs sourced from the owner's land, therefore building running costs are extremely low.

11 User assessment, actual consumption

Per (10.2) above, actual energy use is difficult to accurately report. For the publication linked below the owner estimated that his monthly bills are int eh region of £35/month in winter.

12 Existing studies, publications

Passivhaus Plus Magazine Article, Jan 2021 https://passivehouseplus.ie/magazine/new-build/highland-warrior-scottish-passivehouse-built-with-innovative-local-timber-system