

Project Documentation Gebäude-Dokumentation

Abstract | Zusammenfassung



North Elevation / Nordansicht

WHAKATŪ PASSIVHAUS – Nelson, New Zealand

Data of building | Gebäudedaten

Year of construction Baujahr	2022		
U-value external wall U-Wert Außenwand	0.211 W/(m ² K)	Space heating Heizwärmebedarf	10 kWh/(m²a)
U-value basement U- Wert Kellerdecke	0.205 W/(m ² K)	Primary Energy Renewable (PER) Erneuerbare Primärenergie (PER)	44.43 kWh/(m ² a)
U-value roof U-Wert Dach	0.197 W/(m ² K)	Generation of renewable Energy Erzeugung erneuerb. Energie	7.12 kWh/(m ² a)
U-value window U-Wert Fenster	1.06 W/(m ² K)	Non-renewable Primary Energy (PE) Nicht erneuerbare Primärenergie (PE)	92.42 kWh/(m ² a)
Heat recovery Wärmerückgewinnung	89 %	Pressurization test n Drucktest n ₅₀	0.31 h ⁻¹

Special features Besonderheiten

Certified as a 10 Star Homestar building by the New Green Building Council (the highest possible rating).

50

Von Neuseeland als 10-Sterne-Homestar Gebäude zertifiziert
Green Building Council (die höchstmögliche Bewertung).

Brief Description

WHAKATŪ PASSIVHAUS

This house was designed with the intent to meet our obligations to keep global warming under 1.5 degrees. The passivhaus standard was adopted as a mechanism to ensure that operational carbon was kept to a minimum whilst maintaining a comfortable indoor environment.

The added challenge of this project was to intentionally reduce the amount of concrete used and demonstrate in the process that light weight timber construction can easily meeting the passivhaus standard without the need for thermal mass.

Kurzbeschreibung

WHAKATŪ PASSIVHAUS

Dieses Haus wurde mit der Absicht entworfen, unseren Verpflichtungen nachzukommen, die globale Erwärmung unter 1,5 Grad zu halten. Der Passivhaus-Standard wurde als Mechanismus übernommen, um sicherzustellen, dass der CO₂-Ausstoß im Betrieb auf ein Minimum reduziert und gleichzeitig ein angenehmes Raumklima aufrechterhalten wird.

Die zusätzliche Herausforderung dieses Projekts bestand darin, den Betoneinsatz bewusst zu reduzieren und dabei zu zeigen, dass Holzleichtbauweise problemlos den Passivhausstandard erfüllen kann, ohne dass thermische Masse erforderlich ist.

Responsible project participants Verantwortliche Projektbeteiligte

Architect Entwurfsverfasser	Nathan Edmondston
Implementation planning Ausführungsplanung	Nathan Edmondston
Building systems Haustechnik	Fantech NZ Ltd
Structural engineering Baustatik	Potius Building Systems
Building physics Bauphysik	Nathan Edmondston
Passive House project planning Passivhaus-Projektierung	Nathan Edmondston
Builder Bauherr	Basham Building Ltd www.bashambuilding.co.nz

Certifying body Zertifizierungsstelle

Sustainable Engineering Ltd
www.sustainableengineering.co.nz

Certification ID Zertifizierungs ID

7065

Project-ID (www.passivehouse-database.org)
Projekt-ID (www.passivhausprojekte.de)

Author of project documentation Verfasser der Gebäude-Dokumentation

Nathan Edmondston

Date
Datum

Signature
Unterschrift

07 August 2023



1. Exterior photos - Ansichtsfotos



South Elevation



North Elevation looking West

2. Interior photos - Innenfoto exemplarisch




Main Bedroom




Kitchen

3. Sections - Schnittzeichnung




Section through the stairs




Section through bedroom

4. Floor plans - Grundrisse




Ground Floor Plan



First Floor Plan

5. Floor slab/ basement ceiling construction including insulation Konstruktion der Bodenplatte




Typical Footing Detail

Suspended timber floors were used for this project to reduce the need for excavations and the use of concrete. The floor was constructed as 4 prefabricated panels and delivered to site with the PUR insulation sprayed onto the underside of the 25mm plywood floor. Floor joist are 190mm deep. Once on site, a ply lining was installed to the underside of the joists and the remaining floor cavity was filled with Jet Stream Max blown-in insulation.

The insulation to the edge between the boundary joist and the packer was installed separately before final wall underlays were installed.

Assembly no.						Interior insulation?
03ud Suspended Floors						
Heat transmission resistance [m ² K/W]						
Orientation of building element: 3-Floor		interior R _{si}		0.17		
Adjacent to: 1-Outdoor air		exterior R _{se}		0.04		
Area section 1	λ [W/(mK)]	Area section 2 (optional)	λ [W/(mK)]	Area section 3 (optional)	λ [W/(mK)]	Thickness [mm]
Ply	0.130					7
Heatlok HFO PUR Insulation	0.023	Timber	0.130			50
GlassfibreKnaufJetStream MaxBlown28kg/m3	0.032	Timber	0.130			140
Ply	0.130					25
Percentage of sec. 1		Percentage of sec. 2		Percentage of sec. 3		Total
85%		15.0%				22.2 cm
U-value supplement			U-value: 0.205 W/(m ² K)			

6. Wall construction including insulation - Konstruktion der Außenwände




Plan Detail – External Corner to Bathroom.

All external walls are at least 190mm thick – the detail above is through the bathroom on the exterior wall that is packed a further 45mm to allow for the installation of plasterboard. The walls were prefabricated off site with 190mm top and bottom plates and a double wall between. Studs were at 600mm centres with the internal studs being offset 300mm from the external stud to reduce thermal bridging.

Like the floor, the PUR insulation was sprayed onto the back of the rigid air barrier in the factory with the remainder of the Jet Stream Insulation being installed once the airtightness layer was installed.

Assembly no.		Building assembly description		Heat transmission resistance [m ² K/W]		Interior insulation?	
01ud		Exterior Walls Potius					
Orientation of building element: 2-Wall		Adjacent to: 1-Outdoor air		interior R _{si}	0.13		
				exterior R _{se}	0.04		
Area section 1	λ [W/(mK)]	Area section 2 (optional)	λ [W/(mK)]	Area section 3 (optional)	λ [W/(mK)]	Thickness [mm]	
Strandboard	0.130					8	
Heatlok HFO PUR Insulation	0.023	Timber	0.130			40	
GlassfibreKnaufJetStream MaxBlown28kg/m3	0.032	Timber	0.130			50	
GlassfibreKnaufJetStream MaxBlown28kg/m3	0.032					10	
GlassfibreKnaufJetStream MaxBlown28kg/m3	0.032	Timber	0.130			90	
Ply	0.130					12	
Percentage of sec. 1		Percentage of sec. 2		Percentage of sec. 3		Total	
84%		16.0%		0.0%		21.0 cm	
U-value supplement		W/(m ² K)		U-value: 0.211		W/(m ² K)	


7. Roof construction including insulation - Konstruktion des Daches



The raking roof panels are made up of 190 x 45lvl rafters at 600mm centres with the same insulation build up in the walls and the floors.

Assembly no.		04ud Potius Roof				Interior insulation?
Orientation of building element		1-Roof				
Adjacent to		1-Outdoor air				
Heat transmission resistance [m²K/W]						
		interior R _{si}		0.10		
		exterior R _{se}		0.04		
Area section 1	λ [W/(mK)]	Area section 2 (optional)	λ [W/(mK)]	Area section 3 (optional)	λ [W/(mK)]	Thickness [mm]
Strandboard	0.130					8
Heatlok PUR Insulation	0.023	Timber	0.130			50
GlassfibreKnaufJetStream MaxBlown28kg/m3	0.032	Timber	0.130			140
Still Air Layer	0.210	Timber	0.130			35
Ply	0.130					12
Percentage of sec. 1		Percentage of sec. 2		Percentage of sec. 3		Total
87%		13.5%				24.5 cm
U-value supplement		W/(m²K)		U-value:		0.197 W/(m²K)

8. Window and window installation including glass Ug / g-value and frame performance - Fenster und Fenster-Einbau



All windows and doors are Gealan S 9000 uPVC frames with triple glazing. The U-value of the frames typically sits between 0.95W/(m²K) to 1.2W/(m²K). The glass has a Ug of 0.525 W/(m²K) and a G-value of 52.57%.


9. Air leakage testing - Beschreibung der luftdichten Hülle

Summary

 FanTestic	version: 5.11.2.	licensed to: THERMFiT
Test date: 2022-07-02	By: Malcolm Pasley	
Customer:		
Building Lot Number:		
Building address:	1 Crathie Place Nelson,	

Building and Test Information	
Test file name:	1 Crathie Place Test 5
Building volume [m ³]:	312.7
Envelope Area [m ²]:	255.2
Floor Area [m ²]:	107.2
Building Height (from ground to top) [m]:	59

Results	
Air flow at 50 Pa, Q ₅₀ [m ³ /h]	98.155
Air changes, n ₅₀	0.31
Equivalent leakage area at 50 Pa [cm ²]	14.25
Permeability at 50 Pa [m ³ /h/m ²]	0.385






Photo 7: Photo of head of window from the inside. Window flashing tape can be seen around the opening and insulation used as packer when window was installed.



Photo 8: Photo of main bedroom window with foam air seal installed.



Photo 9: Photo of hinge side of main bedroom window with foam air seal installed.



Photo 11: Photo of northern kitchen window. Window airtape has just been installed over foam airtape to connect window frame to intello.



Photo 12: Photo of southern kitchen window. Window airtape has just been installed over foam airtape to connect window frame to intello.



Photo 13: Photo of upper level northern window showing interior jamb insulation install prior to timber reveals being installed.

10. MVHR - Lüftungsgerät



Photo 1: Ventilation extract above shower to the west. Also, packing over intake for installation of plasterboard and insulation.



Photo 2: Ventilation intake in south wall of MHRV cupboard. Pipe sealed to intake and taped in place.



Photo 3: MHRV unit installed in cupboard. Ventilation pipes starting to be installed.



Photo 4: More ventilation pipes (flow and return) coming out of the space above the MHRV cupboard into the bulkhead space.



Photo 5: Rise to upper level visible for MHRV pipes to service bedrooms and bathroom on the upper level. Also visible here is the hotwater waste heat recovery pipe.



Photo 6: MHRV extract and intake pipes at project completion.



Photo 7: G4 filter installed in the Zehnder Unit.





Photo 8: F7 filter installed in the Zehnder Unit.




Photo 9: Zehnder Unit.

The ventilation system used was the Zehnder ComfoAir Q350 which has 89% efficiency.

11. Ventilation ductwork - Lüftungsplanung Kanalnetz



Floor plans above showing generic layout for the ventilation pipework around the building.



3D schematic showing the reticulated pipework for the ventilation system – this was all modelled in BIM prior to construction to ensure everything would fit in the confined space.

12. Heating systems - Wärmeversorgung



The only heat appliance provided is a portable oil column heater which was not required in 2023.

13. Building costs - Baukosten

N/A

14. Publications featuring the building - Literatur

- Also certified with a 10 Homestar Rating and will feature on the NZGBC website.

15. PHPP-Ergebnisse

Passive House Verification



Architecture: Nathan Edmondston
 Street: _____
 Postcode/City: 7010 Nelson
 Province/Country: _____ NZ-New Zealand

Energy consultancy: Nathan Edmondston
 Street: _____
 Postcode/City: 7010 Nelson
 Province/Country: _____ NZ-New Zealand

Year of construction: 2022
 No. of dwelling units: 1
 No. of occupants: 2.5

Building: Whakatu Passivhaus
 Street: _____
 Postcode/City: 7010 Nelson
 Province/Country: _____ NZ-New Zealand

Building type: 1 Residential building
 Climate data set: NZ0012a-Nelson
 Climate zone: 4: Warm-temperate Altitude of location: 59 m

Home owner / Client: Yuki Fukuda
 Street: _____
 Postcode/City: 7010 Nelson
 Province/Country: _____ NZ-New Zealand

Mechanical engineer: (Builder) Basham Building Limited
 Street: 99 Cambria Street, The Wood,
 Postcode/City: 7010 Nelson
 Province/Country: _____ NZ-New Zealand

Certification: Sustainable Engineering Ltd
 Street: 65B Hungerford Road
 Postcode/City: 6023 Houghton Bay
 Province/Country: Wellington NZ-New Zealand

Interior temperature winter [°C]: 20.0 Interior temp. summer [°C]: 25.0
 Internal heat gains (IHG) heating case [W/m²]: 2.6 IHG cooling case [W/m²]: 3.8
 Specific capacity [Wh/K per m² TFA]: 60 Mechanical cooling: _____

Specific building characteristics with reference to the treated floor area

		Treated floor area m²		Criteria	Alternative criteria	Fulfilled? ²
Space heating	Heating demand kWh/(m²a)	106.8	≤	15	-	yes
	Heating load W/m²	9.97	≤	-	10	-
Space cooling	Cooling & dehum. demand kWh/(m²a)	-	≤	-	-	-
	Cooling load W/m²	-	≤	-	-	-
	Frequency of overheating (> 25 °C) %	9.54	≤	10	-	yes
	Frequency of excessively high humidity (> 12 g/kg) %	0.26	≤	20	-	yes
Airtightness	Pressurization test result n ₅₀ 1/h	0.31	≤	0.6	-	yes
Non-renewable Primary Energy (PE)	PE demand kWh/(m²a)	92.42	≤	-	-	-
Primary Energy Renewable (PER)	PER demand kWh/(m²a)	44.43	≤	60	60	yes
	Generation of renewable energy (in relation to projected building footprint area)	7.12	≥	-	-	-

* Empty field: Data missing; -: No requirement

I confirm that the values given herein have been determined following the PHPP methodology and based on the characteristic values of the building. The PHPP calculations are attached to this verification.

Task: 2-Certifier First name: Jason Surname: Quinn
 Certificate ID: _____ Issued on: 02/11/22 City: Wellington

Passive House Classic? **yes**
 Signature: _____

