

Template project documentation

Project Documentation Gebäude-Dokumentation



1 Abstract / Zusammenfassung



Detached house Enerphit, Sheffield England

1.1 Data of building / Gebäudedaten

Year of construction/ Baujahr	2017	Space heating / Heizwärmebedarf	18 kWh/(m²a)
U-value external wall/ U-Wert Außenwand	0.11 W/(m²K)		
U-value ground floor/ U-Wert Kellerdecke	0.31 W/(m²K)	Primary Energy Renewable (PER) / Erneuerbare Primärenergie (PER)	69kWh/(m²a)
U-value roof/ U-Wert Dach	0.108 W/(m²K)	Generation of renewable energy / Erzeugung erneuerb. Energie	33kWh/(m²a)
U-value window/ U-Wert Fenster	0.9 W/(m²K)	Non-renewable Primary Energy (PE) / Nicht erneuerbare Primärenergie (PE)	73kWh/(m²a)
Heat recovery/ Wärmerückgewinnung	82%	Pressure test n ₅₀ / Drucktest n ₅₀	0.3 h-1
Special features/ Besonderheiten	4Kv Solar PV array		

1.2 Brief Description ...

Enerphit - Sheffield

This 4 bedroom detached house is the first Passive House retrofit building to be completed in Sheffield and the wider area. It has a treated floor area of 158m². It was originally the vicarage to St Bartholemews church located on the same street. The building is a south east facing to the living accommodation and of solid construction with a raft foundation. The loft space is used for ventilation equipment and a mezzanine play area serving the children's bedrooms.

The original building was largely unchanged other than slight reduction in north facing window area and demolition of external concrete canopy and adjoining out house to simplify external insulation.

The existing masonry structure was externally insulated and overclad in Siberian larch. The roof was also overlaid with insulation creating a warm roof. The floor was overlaid with insulation requiring door openings to be raised.

New triple glazed windows were installed in projecting timber boxings

Air tightness was achieved through a mixture of air tight tapes and liquid applied air tightness paint and internal plaster finish.

The main entrance canopy was replaced with a free standing canopy to omit cold bridges.

1.3 Responsible project participants / Verantwortliche Projektbeteiligte

Architect/
Entwurfsverfasser Daniel Bilton, Bilton Design Ltd
<https://www.biltondesign.uk>

Implementation planning/
Ausführungsplanung Daniel Bilton, Bilton Design Ltd
<https://www.biltondesign.uk>

Building systems/
Haustechnik Daniel Bilton, Bilton Design Ltd
<https://www.biltondesign.uk>

Structural engineering/
Baustatik Chris Simm
Peak engineers

Building physics/
Bauphysik Daniel Bilton, Bilton Design Ltd
<https://www.biltondesign.uk>

Passive House project
planning/
Passivhaus-Projektierung Daniel Bilton, Bilton Design Ltd
<https://www.biltondesign.uk>

Construction management/
Bauleitung Daniel Bilton, Bilton Design Ltd
<https://www.biltondesign.uk>

Certifying body/
Zertifizierungsstelle Mead Consulting
<http://www.meadconsulting.co.uk/>

Certification ID/
Zertifizierungs ID Project-ID (www.passivehouse-database.org) 6357
Projekt-ID (www.passivehouse-database.org)

Author of project documentation /
Verfasser der Gebäude-Dokumentation Daniel Bilton, Bilton Design Ltd
<https://www.biltondesign.uk>

Date, Signature/
Datum, Unterschrift 16/10/20



2 Views



South West elevation



North East Elevation

South East (rear) elevation



North west elevation






Hallway - the internal masonry walls form cold bridges, so the stair wall support was replaced with a hanging detail, removing the cold bridge and opening up the hallway. Air tightness tapes and paint can be seen in the background around the front door frame and projecting boxings.

3 - Sectional Drawing

Cutaway showing overall strategy




A

Utility/Kitchen/Dining


1:100

Section showing air tight line and continuous insulation line which wraps externally around the building. The perimeter insulation extends from 600-900mm below ground floor level. The existing raft foundation slab was overlaid with a 100mm PIR insulation and floating T&G timber floor over.

4 .Floor Plans



Ground floor plan, which shows the external insulation and cladding wrapping around the existing masonry structure. The existing plan suited an enerphit conversion as the living spaces faced SSE and the stairs/wc & utility to the north side.




First Floor plan - the main change to this plan was moving of a window from the east side to the south (W14). The original pitched roof to the dining room was roofed to facilitate this, and replaced with a flat roof with a sedum/biodiverse covering.



External insulation being installed

5.1 - Wall/slab junction




D-p01

Typical GF perimeter

1:10

The existing walls were over clad with 240mm EPS and 50mm Rockwool slab between Larsen trusses supporting the outer layers of battens to which horizontal Larch rainscreen cladding was fixed. Higher density EPS was used to the building perimeter, extending between 400-900mm below DPC to mitigate the external wall cold bridge.

5.2 - Wall/roof junction




Roof Eaves detail - Note the mineral fibre insulation providing fire resistant layer over the wall and roof EPS insulation
 The existing roof was overlaid with 18mm melamine faced P5 T&G chipboard, jointed glued and taped (3M sheathing tape) and perimeter taped to rendered and primed masonry walls (proclima tapes)



Air tight roof deck in place being over laid with 240mm EPS

5.4 - Window details



Window details -

Rationell Aura Plus windows - triple glazed windows with composite timber/aluminium frames. Centre pane U-value of 0.52W/M²K, G-value 0.53 o/a U-value 0.83-0.84W/M²K.

Note the mineral fibre insulation layer is returned around the window reveals to encapsulate the EPS in fire resistant material


The window reveals internally were lined with Marmox insulated board with skim finish to reduce cold bridging.



Weather proof membrane installed over mineral fibre insulation, returned into window reveals.

At least one opening light was provided to living spaces

6 - Air tight envelope



Roof - Melamine faced particle board deck with glued T&G joints, taped externally, perimeter taped to primed rendered masonry using Proclima tapes.

Walls - wet plastered internally, junctions with window boxings sealed with Blower proof paint, windows frames taped to boxings with Proclima tapes.

Floor - reinforced concrete raft - junction with walls - Blower proof paint.

Joist ends - Blower proof paint.

6.1 - Pressure test

DETAILS OF TESTED BUILDING

Dwelling Tested:	73, Burgoyne Road, Sheffield, South Yorkshire, S6 2XR	Nett Floor Area, A_k:	88.3 m ²
Est. Year Built:	2019	Volume, V:	429.0 m ³
Test Date:	16 th September 2019	Geometry Prepared By:	Mr Dan Bilton of Bilton Design
Building Heating:	Gas	Geometry Verified By:	Marc Cowlin of Stroma Built Environment
Building Ventilation:	System 4 - Continuous mechanical supply and extract ventilation with heat recovery	Test Method:	B (Building envelope)
		Test Engineer:	David Tetchner (ATTMA Level 2)

INTERPRETATION OF RESULTS

The airflow rate through the envelope of the building/zone was determined at a pressure differential of 50Pa; this result is expressed as an airflow rate per m³ of useable building volume (i.e. excluding floor and wall voids). For more information on the calculations used to determine the air change rate please visit:

http://www.stroma.com/downloads/air_permeability_calculation_v3.pdf

RESULTS AND SUMMARY

The dwelling's air change rate was determined by means of averaging the results from both a pressurisation test. The initial normalised air flow at a pressure differential of 50 Pascals (Q_{50}) was established in accordance with the required test methodology of ATTMA TSL1, in conjunction with the methodology for the volume calculation of the building as outlined within "Passivhaus primer: Airtightness Guide Airtightness and air pressure testing in accordance with the Passivhaus standard". The results attained from the tests were:-

<i>Depressurisation:</i>	Air Change Rate, n_{50}:	0.33h⁻¹ @ 50 Pa
<i>Pressurisation:</i>	Air Change Rate, n_{50}:	0.28h⁻¹ @ 50 Pa
Average:	Air Change Rate, n_{50}:	0.31h⁻¹ @ 50 Pa


This is below the target level of 0.60h⁻¹ at 50 Pa specified, therefore passing the criteria, providing this test was completed at the final state of completion.

Stroma Built Environment is a UKAS accredited testing laboratory No. 2731, and ATTMA registered company.

7 - Vent System Glen Dimplex ZL400VF

Heat recovery rate - 84%
Specific fan power - 0.35Wh/m³

3D layout - Supply pipework shown Blue, Extract Red



FINAL PROTOCOL WORKSHEET for Ventilation Systems: Initial Start-up
Supply- / Extract-Air Ventilation System with Heat Recovery

Project

Object: 0

Location Street, No.: 73

Location Postcode, Town: S6 3QB

Building Owner Name: D Bilton

Building Owner Phone No.: 07940 965922

Year of Construction: 1970

Initial Start-up

Company: Bilton Design Ltd

Person in Charge: D Bilton

Street, No.: 73 Burgoyne rd

Postcode, City: Sheffield S6 3QB

Phone No.: 07940 965922

Date: 16/03/2020

Ventilation System

Manufacturer: Glen Dimplex

Product Name: Xpelair Xcell1400

Unit No.: ZL400vf

Control No.:

1. Record of the air flow volumes, supply and extract air

Nr. Room	Design	Measurement 1			Measurement 2			Measurement 3			Type of Valve	Adjustment	Flow-Through V _{THROUGH} m³/s	Noise dB(A)	Filter Grade	Filter Clean?
		V _{su} m³/h	V _{ex} m³/h	V _{THROUGH} m³/h	V _{su} m³/h	V _{ex} m³/h	V _{THROUGH} m³/h	V _{su} m³/h	V _{ex} m³/h	V _{THROUGH} m³/h						
1 Kitchen			32		82		46		31		Air disk extrac	2x10mm	1.5	27.3	G4	yes/no
2 Dining				32												yes/no
3 Lounge	41				63		50		43		Air disk supply	17mm	1.5	33.9		yes/no
4 Study	15				28		24		15		Air disk supply	12mm	1.2	33.7		yes/no
5 Hall				24												yes/no
6 WC			14		24		10		15		Air disk extrac	12mm	1.2	28.8		yes/no
7 Utility			20		26		16		19		Air disk extrac	13mm	1.4	27.3	G4	yes/no
8 Bedroom 1	20				25		8		17		Air disk supply	15mm	1.1	25.4		yes/no
9 Bedroom 2	12				21		15		11		Air disk supply	11mm	1.0	27.6		yes/no
10 Bedroom 3	16				28		14		15		Air disk supply	11mm	1.3	26.9		yes/no
11 Bedroom 4	16				32		15		16		Air disk supply	10mm	1.5	25.6		yes/no
12 Landing				44												yes/no
13 Bathroom			34		17		20		28		Air disk extrac	18mm	1.5	25.1		yes/no
14 Ensuite			20		22		16		24		Air disk extrac	17mm	1.4	28.3		yes/no
15																yes/no
16																yes/no
17																yes/no
18																yes/no
19																yes/no
20																yes/no
sum:		120.00	120.00	100.00	197.00	171.00	126.00	108.00	117.00	117.00			---	---	---	---

2. Balance of airflow volume

	Measurement 1		Measurement 2		Measurement 3		Disbalance	Type of Control	Adjustment	Noise Measurement dB(A)	Filter Grade	Filter Clean?
	V _{air} m³/h	V _{rel} m³/h	V _{air} m³/h	V _{rel} m³/h	V _{air} m³/h	V _{rel} m³/h						
1 fresh air inlet	187	---	127	---	121	---	2%	Digital	na	na	G1	yes
2 exhaust air outlet	---	168	---	120	---	119		Digital	na	na	-	yes/no

3. Initial start-up accomplished according to manufacturer's specifications:

yes

Signature: David Bilton

7 - Heat Supply

The house was originally fitted with a condensing combi boiler which was re-used to supply hot water and heating. Space heating is provided via towel radiators in bathrooms, one radiator in the hallway and the rest of the house is heated via a wet heater battery on the ventilation supply ductwork, positioned after the pollen filter.



Duct heater fed from Condensing Combi Boiler

EnerPHit Verification

Photo or Drawing		Building: The Vicarage	
		Street: 73 Burgoyne Rd	
Postcode/City: S6 3QB Sheffield		Province/Country: Walkley South Yorkshire	
Building type: Residential		Climate data set: GB0012a-Waddington	
Climate zone: 3: Cool-temperate		Altitude of location: 88 m	
Home owner / Client: D J Bilton		Street: 73 Burgoyne rd	
Postcode/City: S6 3QB		Province/Country:	
Architecture: Bilton Design Ltd		Mechanical engineer:	
Street:		Street:	
Postcode/City:		Postcode/City:	
Province/Country:		Province/Country:	
Energy consultancy: Bilton Design Ltd		Certification:	
Street: 73 Burgoyne Rd		Street:	
Postcode/City: S6 3QB		Postcode/City:	
Province/Country: S Yorks England		Province/Country:	
Year of construction: 1950	Interior temperature winter [°C]: 20.0	Interior temp. summer [°C]: 25.0	
No. of dwelling units: 1	Internal heat gains (IHG) heating case [W/m²]: 2.4	IHG cooling case [W/m²]: 2.4	
No. of occupants: 3.0	Specific capacity [Wh/K per m² TFA]: 204	Mechanical cooling:	

Specific building characteristics with reference to the treated floor area						
				Criteria	Alternative criteria	Fulfilled? ²
Space heating	Treated floor area m²	158.0				
	Heating demand kWh/(m²a)	18	≤	25	-	yes
	Heating load W/m²	11	≤	-	-	
Space cooling	Cooling & dehum. demand kWh/(m²a)	-	≤	-	-	-
	Cooling load W/m²	-	≤	-	-	
	Frequency of overheating (> 25 °C) %	0	≤	10	-	yes
	Frequency of excessively high humidity (> 12 g/kg) %	0	≤	20	-	yes
Airtightness	Pressurization test result n ₅₀ 1/h	0.3	≤	1.0	-	yes
Non-renewable Primary Energy (PE)	PE demand kWh/(m²a)	73	≤	-	-	-
	PER demand kWh/(m²a)	69	≤	64	69	
Primary Energy Renewable (PER)	Generation of renewable energy (in relation to projected building footprint area) kWh/(m²a)	33	≥	-	7	yes

² Empty field; Data missing; -: No requirement

I confirm that the values given herein have been determined following the PHPP methodology and based on the characteristic values of the building. The PHPP calculations are attached to this verification.		EnerPHit Classic?	yes
Task:	First name:	Surname:	Signature:

PHPP Verification sheet. Due to the good U-values, minimal cold bridging and good air test result this wasn't far of a Passivhaus new build performance