

# **Test Report**

# Airtightness test of the vapour control layer including connections System "INTELLO X"

# Manufacturer: pro clima Moll bauökologische Produkte GmbH

Airtightness system: Surface sealing

Darmstadt 10.05.2023

Passive House Institute Rheinstr. 44/46 64291 Darmstadt, Germany www.passiv.de



Commissioned by: Moll bauökologische Produkte GmbH

Rheintalstr. 35-43 68723 Schwetzingen

Germany

Product: Airtightness system consisting of

1. pro clima INTELLO X: humidity variable hydrosafe vapour control layer and airtightness membrane

pro clima CONTEGA SOLIDO IQ: single-sided adhesive tape

3. pro clima ORCON CLASSIC: Solvent-free all-round joint

adhesive

Product name: Tested size:

INTELLO X Metre rolls

#### 1. Introduction

Airtightness across the surface is a central prerequisite for an effective airtightness concept. A good level of airtightness of the building envelope is an essential element for its overall functioning, particularly in energy efficient buildings. This investigation took place under the most realistic possible boundary conditions within the framework of certification as a Passive House component in order to ensure that the tested products function in the installed state. In particular, the connection of the membrane to typical adjacent materials will be examined in the context of certification. With respect to the product system, this test examined the bonding of the membranes with each other and bonding with concrete and hard engineered wood panels (here: OSB), as well as the adhesive materials used.

#### 2. Criteria

The values specified for PH certification of surface sealing can be taken from Table 1 below:

Table 1: Requirement classes for the certification of surface sealing products according to Passive House Institute specifications

	Air permeability based on area @ 50 Pa
Class	[m³/(hm²)]
ph <b>A</b>	≤ 0.10
ph <b>B</b>	≤ 0.18
ph <b>C</b>	≤ 0.25



These apply for the overall performance of a product system specified by the client, consisting of several components.

In addition, comprehensible guidelines/instructions for use must be provided for installation of the product, on which the test setup will be based. These must be made available to all testers.

Testing of moisture permeability and the characteristic values for moisture for different ambient humidity levels do not constitute part of this test.

#### 3. Materials to be tested

The required membranes and adhesive tapes for joining the different connection situations were supplied by the client.

The adhesive tape CONTEGA SOLIDO IQ was used for overlapping joining of the vapour retardant membrane in accordance with the manufacturer's instructions. This adhesive tape was also used for the connection with the OSB panels. The connection with concrete was carried out using the cartridge adhesive ORCON CLASSIC. The use and application of the adhesive tape and joint adhesive took place in accordance with the manufacturer's directions which are described in the instructions for use.

The following products were delivered by the client on 06.04.2023:

- INTELLO X (roll: width 1.5 m, length 50 m)
- CONTEGA SOLIDO IQ with instructions for use
- ORCON CLASSIC with instructions for use

# 4. Setup for the membrane and connections

The membrane roll was cut into two metre pieces which were clamped into the test apparatus across their full width so that they extended on all sides. For sealing, a frame which was identical in construction to the sub-frame of the test apparatus was placed on the apparatus. The frame and counter frames were each equipped with a 5 cm wide sealing surface which served as a support for the airtight membrane. The counter frame was tightened to a defined torque using screws and a torque wrench. Tension-free and uniform installation in the test stand was possible due to the even pressure of the counter frame.

For the connection to OSB or concrete, an OSB panel or a concrete slab was placed in the fixture provided for this purpose. After clamping the piece of membrane, this was cut out along the respective panel. The piece of membrane was thus "suspended in



the air" and surrounded the respective panel. Depending on the type of panel, either CONTEGA SOLIDO IQ (OSB panel) or ORCON CLASSIC (concrete slab) was used to join the membrane with the panel. Here it is important to ensure that the membrane is "suspended in the air" so that pressing the adhesive tape is only possible to a limited extent. This is equivalent to the usual procedure e.g. when laying the membrane in the roof area.

For the connection of the membrane to the concrete, cartridge adhesive ORCON CLASSIC was used. The connections were left at least 15 hours to cure. The climatic conditions of storage correspond to the conditions specified in chapter 7.

Each test setup (membrane to membrane, membrane to OSB and membrane to concrete) was created and tested three times in order to minimise any influences by workers.

#### 4.1 Membrane to membrane

The connection or overlapping of two pieces of membranes was carried out using the adhesive tape CONTEGA SOLIDO IQ in accordance with the manufacturer's instructions. For this, as described in the manufacturer's instructions, the lengths of membrane were placed together overlapping each other by 10 cm and then the adhesive tape was applied equally on both pieces. It was ensured that application of the tape took place with the membrane "suspended in the air" so that pressing the adhesive tape was only possible to a limited extent.



Fig. 1: Connection membrane to membrane with CONTEGA SOLIDO IQ in the test apparatus.



# 4.2 Membrane to OSB panel

The adhesive tape CONTEGA SOLIDO IQ was used for connecting the OSB panel. Here the long sides were connected first. One half of the tape width was attached to the OSB panel and the other half was attached to the membrane. Finally the short sides were joined, overlapping with the full width of the adhesive tape.



Fig. 2: Cut out membrane with OSB panel (left). OSB panel joined to the membrane on all four sides using CONTEGA SOLIDO IQ (right).

#### 4.3 Membrane to concrete

The adhesive ORCON CLASSIC was used for the membrane to concrete connection. ORCON CLASSIC is a "connection-adhesive", applied with an injection cartridge for airtight joints. According to the manufacturer's instructions, a continuous bead of at least 5mm has to be applied, in order to guarantee an airtight joint. The membrane, with a 5cm overlap, was glued to the concrete with a 5mm bead. Following the instructions, the membrane was gently pressed down. According to the manufacturer the adhesive has to dry, in order to create a tight connection. The time of curing depends on the room temperature and the humidity. The manufacturer does not make an exact statement about this. In this case it was left to dry for six days. Airtight measurements or blowing in insulation material before completely curingw can lead to leakages.





Fig. 3: Membrane to concrete connection using ORCON CLASSIC in the test apparatus (left). Membrane to concrete connection in detail (right).

# 5. Test procedure

After setting up in the test stand and attaching the membrane, a measurement was carried out in compliance with DIN EN 12114. For this measurement, the following pressure stages were set for positive and negative pressure: 50, 100, 150, 200, 250, 300, 350 Pa. First the residual leakage of the test stand for all pressure stages was measured and documented for each measurement (reference measurement). For this, the test apparatus was closed using an airtight board. The infiltration air of the test stand determined thus was deducted from the result of the measurement afterwards.

In each measurement, the conveyed volume flow was measured and recorded for each individual pressure difference. With these pairs of measured values, it was possible to calculate the leakage coefficient  $\boldsymbol{c}$  in accordance with DIN EN 12114 Appendix B.

From the two series of reference measurements and the two series of actual measurements, smoothing functions were determined through a regression analysis. After deducting the leakage of the test stand itself (reference measurement), the leakage flow was determined for the reference pressure difference of 50 Pa as an average value of the results from the series of negative and positive pressure measurements. This value was divided by the sample area in order to obtain the specific leakage flow per square metre. The free area of the sample is 1.72 m² or 1.48 m² with deduction of the cut-out for the OSB panel or concrete slab.






Fig. 4: Sketch of the test apparatus with a fixture for the respective panels




Fig. 5: Sketch of the test apparatus with the clamped membrane and inserted panel which is joined to the membrane with adhesive tape (yellow) (left).

Test apparatus sealed with the cover panel for determining the test stand leakage (right).

The measurements of the examined airtightness system took place in the time period from 14.04.2023 to 08.05.2023.



# 6. Test results

The test results are shown in the following tables and figures, sorted according to the connection methods. The requirement classes for the certification of surface sealing systems are additionally entered in the diagrams.

In the following diagrams with a double logarithmic axis scale, some of the measured values that were determined are not recognisable because these are less than the smallest depicted y-axis value.



# 6.1 Membrane to membrane

Connection to	
Membrane on its own	
Membrane to membrane	Х
Membrane to OSB	
Membrane to concrete	

Table 2: Test results of the three measurements with the membrane to membrane connection using CONTEGA SOLIDO IQ

examined area	1,72 r	m²	l					
Bonded using CONTEGA S	SOLIDO IQ							
Pressure stages	Pa	50	100	150	200	250	300	350
INTELLO X to INTELLO X#1	1							
total volume flow	m³/h	0,00	0,14	0,17	0,19	0,21	0,23	0,24
test stand leakage	m³/h	0,00	0,13	0,15	0,17	0,18	0,20	0,21
specific air volume flow	m³/h	0,01	0,01	0,02	0,02	0,03	0,03	0,03
leakage volume flow based on area	m³/(h m²)	0,00	0,01	0,01	0,01	0,01	0,02	0,02
INTELLO X to INTELLO X #2	2							
total volume flow	m³/h	0,01	0,15	0,18	0,20	0,22	0,24	0,25
test stand leakage	m³/h	0,00	0,12	0,15	0,16	0,18	0,19	0,20
specific air volume flow	m³/h	0,02	0,03	0,03	0,04	0,04	0,05	0,05
leakage volume flow based on area	m³/(h m²)	0,01	0,02	0,02	0,02	0,02	0,03	0,03
INTELLO X to INTELLO X#3	3							
total volume flow	m³/h	0,00	0,13	0,15	0,17	0,18	0,20	0,21
test stand leakage	m³/h	0,01	0,14	0,16	0,18	0,19	0,21	0,22
specific air volume flow	m³/h	0,00	0,00	0,00	0,00	0,00	0,00	0,00
leakage volume flow based on area	m³/(h m²)	0,00	0,00	0,00	0,00	0,00	0,00	0,00

Average  $Q50 \, (\text{PHI - assessment}) \qquad \textbf{0,00} \qquad \text{m}^3/(\text{h m}^2)$  resulting in an airtightness class of  $\textbf{A} \qquad \text{according to PHI} \qquad Q50 \leq 0,1$ 






Fig. 6: Series of measurements for the sample "INTELLO X to INTELLO X #1". The Certification Classes A to C according to the PHI are entered in addition.




Fig. 7: Series of measurements for the sample "INTELLO X to INTELLO X #2". The Certification Classes A to C according to the PHI are entered in addition.






Fig. 8: Series of measurements for the sample "INTELLO X to INTELLO X #3". The Certification Classes A to C according to the PHI are entered in addition.



# 6.2 Membrane to OSB


Connection to	
Membrane on its own	
Membrane to membrane	
Membrane to OSB	Х
Membrane to concrete	

Table 3: Test results of the three measurements with the membrane joined to the OSB using CONTEGA SOLIDO IQ

examined area	1,48 m²

Bonded	usina	CONTEGA	SOLIDO IQ
Dollaca	usiliu	CONTLUA	SOLIDO IQ

Pressure stages	Pa	50	100	150	200	250	300	350
INTELLO X to OSB #1								
total volume flow	m³/h	0,00	0,15	0,19	0,23	0,27	0,31	0,34
test stand leakage	m³/h	0,01	0,14	0,16	0,18	0,19	0,20	0,22
specific air volume flow	m³/h	0,00	0,00	0,00	0,03	0,11	0,36	0,99
leakage volume flow based on area	m³/(h m²)	0,00	0,00	0,00	0,02	0,07	0,24	0,67
INTELLO X to OSB #2			•		•	м	м	
total volume flow	m³/h	0,08	0,25	0,30	0,34	0,37	0,41	0,44
test stand leakage	m³/h	0,06	0,19	0,21	0,22	0,23	0,25	0,25
specific air volume flow	m³/h	0,02	0,05	0,07	0,09	0,12	0,15	0,17
leakage volume flow based on area	m³/(h m²)	0,02	0,03	0,05	0,06	0,08	0,10	0,12
INTELLO X to OSB #3			•	•	•	•	•	
total volume flow	m³/h	0,03	0,18	0,23	0,27	0,30	0,33	0,36
test stand leakage	m³/h	0,00	0,13	0,15	0,17	0,18	0,20	0,21
specific air volume flow	m³/h	0,02	0,05	0,07	0,09	0,11	0,13	0,15
leakage volume flow based on area	m³/(h m²)	0,02	0,03	0,05	0,06	0,07	0,09	0,10








Fig. 9: Series of measurements for the sample "INTELLO X to OSB #1". The Certification Classes A to C according to the PHI are entered in addition.




Fig. 10: Series of measurements for the sample "INTELLO X to OSB #2". The Certification Classes A to C according to the PHI are entered in addition.






Fig. 11: Series of measurements for the sample "INTELLO X to OSB #3". The Certification Classes A to C according to the PHI are entered in addition.

Regarding the measurement "INTELLO X to OSB #1", it should be noted that a bulge (detachment) occurred between the membrane and the adhesive tape at one point (see Figure 12). This could be eliminated by carefully pressing the adhesive tape to the membrane. This effect only occurred on this sample and only became relevant at a pressure of over 300 Pa. Therefore, it is generally important to ensure that the adhesive tape is pressed on very well.



Fig. 12: Leakage measurable with an anemometer at the transition between membrane and adhesive tape before rework. Leakage detectable only at higher pressures



# 6.3 Membrane to concrete

Connection to	
Membrane on its own	
Membrane to membrane	
Membrane to OSB	
Membrane to concrete	Х

Table 4: Test results of the three measurements with the membrane joined to concrete using ORCON CLASSIC

examined area	1,48 m²
---------------	---------

Bonded using ORCON CLASSIC

Pressure stages	Pa	50	100	150	200	250	300	350
INTELLO X to concrete #1			•	•	•	•	•	
total volume flow	m³/h	0,00	0,11	0,13	0,15	0,16	0,17	0,18
test stand leakage	m³/h	0,00	0,14	0,16	0,18	0,20	0,22	0,23
specific air volume flow	m³/h	0,00	0,00	0,00	0,00	0,00	0,00	0,00
leakage volume flow based on area	m³/(h m²)	0,00	0,00	0,00	0,00	0,00	0,00	0,00
INTELLO X to concrete #2	•			•		м	4	
total volume flow	m³/h	0,00	0,12	0,14	0,16	0,17	0,18	0,20
test stand leakage	m³/h	0,00	0,14	0,16	0,18	0,19	0,21	0,22
specific air volume flow	m³/h	0,00	0,00	0,00	0,00	0,00	0,00	0,00
leakage volume flow based on area	m³/(h m²)	0,00	0,00	0,00	0,00	0,00	0,00	0,00
INTELLO X to concrete #3	•		•	•	•	•	•	
total volume flow	m³/h	0,00	0,12	0,14	0,16	0,17	0,18	0,19
test stand leakage	m³/h	0,01	0,14	0,16	0,18	0,20	0,21	0,22
specific air volume flow	m³/h	0,00	0,00	0,00	0,00	0,00	0,00	0,00
leakage volume flow based on area	m³/(h m²)	0,00	0,00	0,00	0,00	0,00	0,00	0,00

Ave	rage			
	Q50 (PHI - assessment)	0,00	$m^3/(h m^2)$	
ı	esulting in an airtightness class of	Α	according to PHI	Q50 ≤ 0,1






Fig. 13: Series of measurements for the sample "INTELLO X to concrete #1". The Certification Classes A to C according to the PHI are entered in addition.




Fig. 14: Series of measurements for the sample "INTELLO X to concrete #2". The Certification Classes A to C according to the PHI are entered in addition.






Fig. 15: Series of measurements for the sample "INTELLO X to concrete #3". The Certification Classes A to C according to the PHI are entered in addition.



# 7. Test conditions

The average indoor climate conditions during the measurements and storage were as follows:

Indoor temperature: 19.4 °C Indoor air humidity: 52 % r.H.

#### 8. Measurement devices

A laminar flow element by the company TetraTec® Instruments was used for measuring the volume flow. The differential pressure was measured using an automated performance testing system (APT) by the manufacturer The Energy Conservatory.

Table 5: Overview of the used measurement devices

Name	Device	Serial	Measurement	Measurement
	type	number	range	accuracy
LaminarMasterFlow-	LMF	PH796	0-85 l/min	2% in the range
System				of 8-80 I/min
TEC Automated	APT	0072 4	0-2000 Pa	1 %
Performance Testing				



#### 9. Results

The results of these measurements were compiled and the overall average value was created according to the type of connection. In doing so, the measured value for the membrane on its own (without any joining) was not taken into account because this concerns certification as a system and not material testing only. On average, this resulted in an air permeability value of **0.01** (±0.004) m³/(hm²) standardised for a test pressure of 50 Pa. The certification class "A" was achieved.

Table 6: Overview of the results of the airtightness measurement.

Average value of	m³/(hm²) @ 50 Pa
Membrane to membrane	0.00
Membrane to OSB	0.01
Membrane to concrete	0.00
Overall	0.01 (±0.004)

Table 7: Requirement class achieved by the examined product for certification as an "Airtightness system surface sealing" according to the specifications of the Passive House Institute

Class	Air permeability based on length @ 50 Pa [m³/(hm²)]	Class achieved
ph <b>A</b>	≤ 0.10	✓
ph <b>B</b>	≤ 0.18	
ph <b>C</b>	≤ 0.25	

Darmstadt, 10.05.2023

Søren Peper

Søren Peper

Passive House Institute