

Project Documentation

1 Abstract / Zusammenfassung



House for rural tourism in Ibero, Navarra, Spain

short text about the characteristics of the building	Attached house. Structure: concrete pillars and beams. Facades: ceramic bricks with mortar in the outside and clay in the inside finished to the inside with a carton-kley board. Finishes: North façade: outside wood fiber isolation with mortar. South façade: a ventilated façade finished with pine wood. Tilted roof: concrete slab, wood fiber inside and XPS outside under ceramic tiles.
Specialties	
U-values (roof, wall, window, floor slab/ basement ceiling)	Roof: 0,111 W/(m²K) Wall: North: 0,199 W/(m²K) South: 0,183 W/(m²K)

	Flor slab: 0,146 W/(m ² K) Basement ceiling: 0,155 W/(m ² K) Window: U _f : 0,93 W/(m ² K) U _g : 0,52 W/(m ² K)
Heat recovery	ComforAir550 by Zehnder
heat supply demand based on PHPP	14,65 kWh/(m ² a)
primary energy demand based on PHPP	88 kWh/(m ² a)
Result of the blower-door-test (n50-value, series of under- and overperssure)	0,615 m ³ /(hm ²)

1.1 Building data

Year of construction: 2016

1.2 Brief description of the construction task

It's a house for short stances situated in an small town 15 km far from Pamplona, in the north of Spain.

The building is situated between other residential buildings, in the center of the village.

It's a three stores building: in the basement the entrance, a garage for two cars (a room for the heating pump) a bedroom with its bathroom and a distributor with a circular stair; in the first floor a living room, a kitchen, a bathroom and a bedroom with its bathroom; and in the second floor four bedrooms with their bathrooms.

The entrance of the house faces north and the south façade looks into a courtyard.

The structure of the building is formed by concrete pillars and beams (even for the tilted roof).

The facades are made with ceramic bricks with mortar in the outside and clay in the inside. The north façade is finished in the outside with a wood fiber isolation with mortar; the south façade is a ventilated façade finished with pine wood. Both are finished to the inside with a carton-kley board.

The building has been used for 16 months, with periodical occupancies by different groups of people, both in winter and in summer with a high comfort and satisfaction degree.

Responsible project participant, certification ID, Passive House Database ID, name

1.3 Responsible project participants

Architects:	BOA arquitectos SLP http://www.boa-arquitectos.com/
Structural engineers:	FS estructuras http://fsestructuras.com/
Technical architect:	Enrique Munguira
Implementation planning:	Progetic http://www.progetic.com/es/
Passivhaus designer :	Iñaki Archanco (BOA arquitectos)
Certifying body	Passive House Institute Darmstadt www.passiv.de
Certification ID	Project-ID (www.passivehouse-database.org) 4864
Author of project documentation:	Iñaki Archanco (BOA arquitectos)

2 Views of the Passive House in Ibero



North façade



South façade



South façade, detail.



Living room



Bedroom





Distributor

3 Sectional drawing of the house in Ibero

LAMINAS


ESTANQUEIDAD	
	YESO EN CARA INTERIOR
	TABLERO OSB CON JUNTAS ENCINTADAS
PARAVAPOR	
	LAMINA PARAVAPOR
IMPERMEABILIZACION	
	LAMINA IMPERMEABLE TRANSPIRABLE



Section 1 through the garage shows the continuity of the thermal envelope. In the north façade we have wood-fiber insulation with a mortar finish. In the south façade the insulation is wood-fiber too, but in a wood ventilated façade system. We have XPS over the roof concrete slab. And we have mineral fiber insulation in the ceiling of the garage, under the concrete slab.


The air tightness is solved with a plaster finish over the brick walls of the facades, and the lower side of the roof concrete slab.

The counter flow heat exchanger is situated in a small room under the highest part of the tilted roof.



Section 2 shows the part of the house with three floors: the house occupies the ground level too.

The continuity of the isolation can be seen too. Under the ground level concrete slab we have EPS.




SECCIÓN 4

Section 4 is a long section. In it we can see both the part of the house with the garage and the part that occupies the three floors. The separation between house and garage was built with a brick wall with plaster in its inner side for the air tightness. Over the plaster we have wood fiber insulation. We have a thermal bridge where the wall between the house and the garage encounters the concrete slab of the ground level.


4 Floor plans of the Passive House in Ibero

Wall types:


M1 FACHADA CALLE Y MEDIANERA DE PIEDRA




M2 MEDIANERA DE PIEDRA




M3 MEDIANERA DE PIEDRA EN GARAJE




M4 FACHADA CALLE EN GARAJES




M5 FACHADA CALLE




M6A FACHADA PATIO CASA NORTE




M6B FACHADA PATIO CASA ESTE




M7 MEDIANERA INTERIOR




T1 TABIQUERÍA INTERIOR




M8 SEPARACIÓN CASA-GARAJE




M9 FACHADA GARAJE-PATIO




T2 MURO PORTANTE INTERIOR






Ground floor plan. West side is occupied by the garage. In the east side we have the entrance of the house, stairs to the upper floors and a bedroom with its bathroom. Windows of the bedroom and bathroom face the south courtyard.



First floor. We find stairs coming from the ground floor and stairs going to the second floor in the living-room. The kitchen is on the west part. In the north part a bedroom with its bathroom. Biggest windows face south.


5 Construction details of the envelope and Passive House technology of the Passive House in Ibero

5.1 Construction including insulation of the floor slab or basement ceiling with connection points of exterior and interior walls



EPS under the concrete slab. The insulation advances under the floor of the garage to reduce the thermal bridge.

5.2 Construction including insulation of exterior walls



Nr. elem. cons.		02ud		FACHADA NORTE SATE		¿Aislamiento interior?	
Resistencia térmica superficial [m²K/W]							
Inclinación del elemento		0,13		interior R _s		0,13	
Adyacente a		0,04		exterior R _s		0,04	


Superficie parcial 1	λ [W/m·K]	Superficie parcial 2 (opcional)	λ [W/m·K]	Superficie parcial 3 (opcional)	λ [W/m·K]	Espesor (mm)
RASEO DE MORTERO	1,400					20
PANEL DE FIBRA DE MADERA	0,042					140
RASEO DE MORTERO	1,300					15
LADRILLO PERFORADO	0,567					110
LUCIDO DE YESO	0,570					15
THERMOFLEX DE GUTEX	0,038	PERFIL GALVANIZADO	50,000			80
PLACA CARTÓN-YESO	0,250					15

Porcentaje superficie parcial 1	100%	Porcentaje superficie parcial 2	0,0%	Porcentaje superficie parcial 3		Total	39,5 cm
---------------------------------	------	---------------------------------	------	---------------------------------	--	-------	---------


Suplemento al valor-U	0,02 W/(m²K)	Valor-U:	0,199 W/(m²K)
-----------------------	--------------	----------	---------------



North façade with wood fiber insulation on the brick wall.



CASA NORTE
FACHADAS



Nº elem. cons.		¿Aislamiento interior?	
03ud		FACHADA SUR VENTILADA	
Resistencia térmica superficial [m²K/W]			
Inclinación del elemento	0,13	interior R _s	0,13
Adyacente a	0,04	exterior R _s	0,04
Superficie parcial 1	λ [W/m·K]	Superficie parcial 2 (opcional)	λ [W/m·K]
TABLERO DE CONIFERA	0,230		
CAMARA	0,108		RASTREL DE PINO
THERMOFLEX DE GUTEX	0,038		RASTREL DE PINO
RASEO DE MORTERO	1,300		
LADRILLO PERFORADO	0,567		
LUCIDO DE YESO	0,570		
THERMOFLEX DE GUTEX	0,038	PERFIL GALVANIZADO	50,000
PLACA CARTÓN-YESO	0,250		
Espesor [mm]			
20			
20			
140			
15			
110			
15			
80			
15			
Porcentaje superficie parcial 1	94%	Porcentaje superficie parcial 2	0,0%
Porcentaje superficie parcial 3	6,5%	Total	41,5 cm
Suplemento al valor-U	W/(m²K)	Valor-U:	0,183 W/(m²K)








The south façade is solved as a ventilated façade: wood panels fixed to wooden strips. These wooden strips are nailed to other wooden strips fixed to the bricks wall. Between the main wooden strips there are wood-fiber panels, and over them a waterproof sheet.

5.3 Construction including insulation of the roof



Nr. elem. cons.

07ud

CUBIERTA

¿Aislamiento interior?

Inclinación del elemento

0,1

Resistencia térmica superficial [m²K/W]

interior R_{si} 0,10

exterior R_{se} 0,04

Adyacente a

0,04

Superficie parcial 1	λ [W/(mK)]	Superficie parcial 2 (opcional)	λ [W/(mK)]	Superficie parcial 3 (opcional)	λ [W/(mK)]	Espesor [mm]
TEJA CERÁMICA	1,000	TEJA CERÁMICA	1,000	TEJA CERÁMICA	1,000	20
CÁMARA DE AIRE	0,245	RASTREL DE PINO	0,230	CÁMARA DE AIRE	0,245	40
POLIESTIRENO	0,038	RASTREL DE PINO	0,230	POLIESTIRENO	0,038	160
ESTRUSIONADO				ESTRUSIONADO		
FORJADO	1,211	FORJADO	1,211	VIGA DE HORMIGÓN	2,300	350
LUCIDO DE YESO	0,570	LUCIDO DE YESO	0,570	LUCIDO DE YESO	0,570	15
ALPHAROCK - E- Z23 DE ROCKWOOL	0,034	ALPHAROCK - E- Z23 DE ROCKWOOL	0,034	ALPHAROCK - E- Z23 DE ROCKWOOL	0,034	160
CÁMARA DE AIRE	0,240	PLACA CARTÓN-YESO	0,250	CÁMARA DE AIRE	0,240	40
PLACA CARTÓN-YESO	0,250	PLACA CARTÓN-YESO	0,250	PLACA CARTÓN-YESO	0,250	15

Porcentaje superficie parcial 1

70%

Porcentaje superficie parcial 2

6,7%

Porcentaje superficie parcial 3

23,7%

Total

80,0

cm

Suplemento al valor-UW/(m²K)

Valor-U: 0,111 W/(m²K)








The roof is a tilted concrete slab and over it two XPS panels were fixed (with wooden strips between the slabs of the second level), and a waterproof screen. Over the last one there are wooden strips and ceramic tiles.




In the connection between the roof and the north façade the wood fiber insulation goes up to the wooden panels of the roof's eaver.





In the south façade the wood fiber panels of the façade go up to cover the front of the XPS panels of the roof.

5.4 Window sections including installation drawing



ID	Descripción	Valor g	Valor-Ug
			W/(m²K)
01ud	4/18/4nl/18/3+3NL	0,50	0,52
02ud	3+3/18/4nl/18/4+4NL	0,50	0,52
03ud	4/18/4nl/18/4nl	0,53	0,53
04ud	6H-Tg18Ar-4HT-Tg18aR-33.2T	0,44	0,54
05ud			
06ud			
07ud			
08ud			
09ud			
10ud			


[illegible]







North façade windows are fixed to the brick wall. The exterior insulation overlaps the windows 'frame. In the inside the airtight is achieved with tapes fixed to the wooden frame and to the plaster of the wall.




In the south façade the airtightness is solved in the same way, and outside the wooden strips of the ventilated façade overlap the windows frame and the waterproof sheet is fixed to the window frame.

6 Description of the airtight envelope; documentation of the pressure test result

The airtightness is solved casting plaster over the brick walls and the concrete slabs of the roof and the basement ceiling. In the points where the continuity of the plaster is broken for the passing of the insulation special sheets are employed:









Cuadro resumen con los principales parámetros obtenidos como resultados del ensayo Blower Door a **Despresurización** realizado:

		Resultados	Intervalo de confianza (95%)	Incertidumbre
V ₅₀	Caudal medio (50 Pa)	328,5 [m ³ /h]	[323,6 333,3]	+/-1,5%
n ₅₀	Renovaciones por hora (50 Pa)	0,609 [h⁻¹]	[0,588 0,629]	+/-3,3%
q ₅₀	Permeabilidad al aire (50 Pa)	0,576 [m ³ /(m ² *h)]	[0,577 0,596]	+/-3,3%
W ₅₀	Tasa específica de filtrado (50Pa)	1,618 [m ³ /(m ² *h)]	[1,564 1,672]	+/-3,3%


Cuadro resumen con los principales parámetros obtenidos como resultados del ensayo Blower Door a **Presurización** realizado:

		Resultados	Intervalo de confianza (95%)	Incertidumbre
V ₅₀	Caudal medio (50 Pa)	334,6 [m ³ /h]	[317,1 353,0]	+/-5,4%
n ₅₀	Renovaciones por hora (50 Pa)	0,620 [h⁻¹]	[0,582 0,658]	+/-6,1%
q ₅₀	Permeabilidad al aire (50 Pa)	0,587 [m ³ /(m ² *h)]	[0,551 0,623]	+/-6,1%
W ₅₀	Tasa específica de filtrado (50Pa)	1,648 [m ³ /(m ² *h)]	[1,547 1,745]	+/-6,1%

Cuadro resumen con los principales parámetros obtenidos como resultados del ensayo Blower Door **Combinado (Presurización + Despresurización)** realizado:

		Resultados	Intervalo de confianza (95%)	Incertidumbre
V ₅₀	Caudal medio (50Pa)	331,5 [m ³ /h]	[320,5 343,0]	+/-3,4%
n ₅₀	Renovaciones por hora (50 Pa)	0,610 [h⁻¹]	[0,585 0,643]	+/-4,7%
q ₅₀	Permeabilidad al aire (50 Pa)	0,582 [m ³ /(m ² *h)]	[0,554 0,609]	+/-4,7%
W ₅₀	Tasa específica de filtrado (50Pa)	1,633 [m ³ /(m ² *h)]	[1,556 1,711]	+/-4,7%


7 Planning of ventilation ductwork (example)



Second floor plan. Blue ducts supply air in the bedrooms. Brown ducts extract the dirt air from bathrooms.




First floor plan. Supply ducts go through the ceiling of the floor to the living-room and bed-room. Extract ducts take air from bath-rooms and the kitchen.



Basement floor plan. The ducts, in the basement floor, go out of the airtight envelope in the garage, and enter again to supply air to the bed-room and extract it from the bath-room and the small store in the entrance.

8. Ventilation plan for the central unit / type / specific values




The counterflow air-to-air heat exchanger used for heat recovery is located in a technical floor under the roof of the house. It's a Zehnder certified machine.

Zehnder ComfoAir 550



Zehnder ComfoAir 550



FALSO TECHO DE PLANTA BAJOCUBIERTA (E:1/25)

From the machine unther the roof the ducts go down to the diferent floors.

Ventilation unit

Zehnder ComfoAir 550

Descriptions

Technical specifications

Heat exchanger:	Plastic
Fans:	EC direct current radial fans
Filters:	Extract air: G4 Outside air: G4 (optional F7 pollen filter)
Condensate connection:	DN 32
Air duct connections:	4 x DN 180 at top DN 125 / 150 / 160
Electrical connection:	230 V, 50 Hz
Temperature range:	Min. 10 °C/max. 40 °C
Acoustic performance (min./max.):	Extract air 28 dB(A)/63 dB(A) Supply air: 35 db(A) / 79 dB(A)
Heat recovery:	Up to 95%
Volumetric flow:	Maximum 550 m ³ /h at 240 Pa external Minimum 50 m ³ /h at 5 Pa external
Power consumption:	
At 225 m ³ /h and 100 Pa:	0.30 W/m ³
Dimensions:	Height: 800 mm Width: 725 mm Depth: 569 mm
Weight:	47 kg

9. Heat supply



For the hot water production a heat-pump is used.


Bomba de calor de 1 compresor hasta aprox. 55 °C tem				
Datos técnicos HPSU Unidad exterior			~1/230 V	
Tipo de unidad exterior	6 kW	7 kW	8 kW	
				
				
Prestaciones				
Potencia Nominal Calefacción A-7/I35 *	kW	4,2	5,1	5,7
Potencia Nominal Calefacción A2/I35 *	kW	5,5	6,6	7,2
Potencia Nominal Calefacción A10/I35 *	kW	8,6	10,1	11,0
COP Nominal A-7/I35 **		2,53	2,70	2,67
COP Nominal A2/I35 **		3,47	3,49	3,34
COP Nominal A10/I35 **		4,94	4,78	4,54
Potencia Nominal Refrigeración A35/I18 *	kW	7,2	8,2	8,4
Potencia Nominal Refrigeración A35/I7 *	kW	5,1	5,9	6,1

It supplies hot water to the post-heating battery of the air exchange system:

Zehnder ComfoPost CW10
Batteria di post trattamento per sistemi di ventilazione comfort

ComfoPost CW10





ELEMENTOS ESQUEMA DE PRINCIPIO	Ref.:	Fcante.:	ELEMENTOS ESQUEMA DE PRINCIPIO	Ref.:	Fcante.:
	--	--		--	--
	--	--		--	--
	--	--		--	--
	--	--		--	--
	--	--		--	--
	--	--		--	--
	--	--		--	--

ELEMENTOS ESQUEMA DE PRINCIPIO	Ref.:	Fcante.:	ELEMENTOS ESQUEMA DE PRINCIPIO	Ref.:	Fcante.:
	--	--		--	--
	--	--		--	--
	--	--		--	--
	--	--		--	--
	--	--		--	--
	--	--		--	--
	--	--			

Cliente :
BOA ARQUITECTOS
Dirección :
Berriobide, 40, oficina 124. Ansoain.

Aceptado Cliente :

Proyecto :
EJECUTIVO Viviendas unifamiliares entre medianeras
Plano :
INSTALACIONES - Esquema hidráulico.

Carrer de Ramon Tund, 100. 3-3.
08006 Barcelona
T. 93 678 22 43
progetic@progetic.com
www.progetic.com



Fecha de creación :
30/01/2015

Tamaño Plano :
Din-A3

Número :

7

Dibujado :

Referencia :

Escala :

--

10. PHPP. Verification sheet.

Comprobación Passivhaus



Edificio:	CASA RURAL LARREBERRI 16-A		
Calle:	C/ LARREBERRI 16-A		
CP / Ciudad:	31173 / IBERO		
País:	ESPAÑA		
Tipo de edificio:	VIVIENDA UNIFAMILIAR ENTRE MEDIANERAS PARA USO COMO CASA RURAL		
Clima:	[ES] - Pamplona, Navarra D1	Altitud del sitio del edificio (en [m] sobre el nivel del mar):	395
Propietario / cliente:	SUGEA HOME SL		
Calle:	C/ OIANONDOA 8, BAJO		
CP / Ciudad:	31013 / BERRIOZAR		
Arquitectura:	BOA ARQUITECTOS SLP		
Calle:	C/ BERRIOBIDE 40, OFICINA 124		
CP / Ciudad:	31013 / ANSOAIN		
Instalaciones:	SOLANO E IRIARTE		
Calle:	C/San Esteban, 11		
CP / Ciudad:	31699 / Zabaldica		
Año construcción:	2014	Temperatura interior invierno:	20,0 °C
Nr. de viviendas:	1	Temperatura interior verano:	25,0 °C
Nr. de personas:	5,0	GIC invierno:	2,1 W/m²
Capacidad específica:	132 Wh/K por m² de SRE	GIC verano:	5,0 W/m²
		Volumen exterior V _e m³:	1067,9
		Refrigeración mecánica:	

Valores característicos del edificio con relación a la superficie de referencia energética y año				
	Superficie de referencia energética	203,3 m²	Requerimientos	¿Cumplido?*
Calefacción	Demanda de calefacción	14,65 kWh/(m²a)	15 kWh/(m²a)	sí
	Carga de calefacción	8,6 W/m²	10 W/m²	sí
Refrigeración	Demanda total refrigeración	kWh/(m²a)	-	-
	Carga de refrigeración	W/m²	-	-
	Frecuencia de sobrecalentamiento (> 25 °C)	8,5 %	-	-
Energía primaria	Calef., ref., deshum., ACS, elect. auxiliar, ilum., aparatos eléct.	88 kWh/(m²a)	120 kWh/(m²a)	sí
	ACS, calefacción y electricidad auxiliar	65 kWh/(m²a)	-	-
	Ahorro de EP a través de electricidad solar	kWh/(m²a)	-	-
Hermeticidad	Resultado ensayo de presión n50	0,6 1/h	0,6 1/h	sí

* Campo vacío: faltan datos; '-': sin requerimiento

Passivhaus?

sí

Confirmamos que los valores aquí presentados han sido determinados siguiendo la metodología PHPP y están basados en los valores característicos del edificio. Los cálculos con PHPP están adjuntos a esta aplicación.

Nombre:

IÑAKI

Apellidos:

ARCHANCO MANCHO

Compañía:

BOA ARQUITECTOS SLP

PHPP Versión 8.5

Número de registro PHPP:

PEPES 200913 25388555 es

Expedido en:

Firma:

11. Construction costs

The house (we call it “the north house”) was built together with a second house (we call it “the east house” and it was certified Enerphit), so the budget was for two houses.

Usable area for both houses:

passivhaus		enerphit	
SUP. ÚTILES CASA NORTE		SUP. ÚTILES CASA ESTE	
GARAJE	43,5	GARAJE	64,10
ENTRADA	2,3	ENTRADA	4,90
CUARTO 1	1,5	CUARTO 1	3,20
DISTRIBUIDOR PB	10,2	DISTRIBUIDOR PB	21,10
DISTRIBUIDOR PBC	7,7	SALA PB	22,80
ESCALERA PB-P1	3,0	DISTRIBUIDOR P1	8,10
ESCALERA P1-PBC	3,0	DISTRIBUIDOR PBC	16,40
ESTAR-COMEDOR	47,6	ESCALERA PB-P1	3,60
COCINA	10,0	ESCALERA P1-PBC	4,20
DORMITORIO 1	15,3	CUARTO 2	2,50
DORMITORIO 2	10,6	ESTAR	28,70
DORMITORIO 3	15,1	COMEDOR	20,30
DORMITORIO 4	14,8	COCINA	8,90
DORMITORIO 5	15,4	DORMITORIO 1	14,30
DORMITORIO 6	14,1	DORMITORIO 2	12,40
BAÑO 1	4,2	DORMITORIO 3	14,50
BAÑO 2	4,8	DORMITORIO 4	17,50
BAÑO 3	4,2	DORMITORIO 5	14,90
INODORO-DUCHA 3	2,7	DORMITORIO 6	12,90
INODORO-DUCHA 4	2,7	DORMITORIO 7	15,20
INODORO-DUCHA 5	2,2	BAÑO 1	4,30
INODORO-DUCHA 6	3,0	BAÑO 2	4,10
TOTAL ÚTIL	237,9	INODORO-DUCHA 1	2,00
		INODORO-DUCHA 3	2,70
		INODORO-DUCHA 4	2,20
		INODORO-DUCHA 5	2,30
		INODORO-DUCHA 6	2,00
		INODORO-DUCHA 7	3,90
		TOTAL ÚTIL	334,00

The final cost of the two buildings was:

2 CASA RURALES EN IBERO

CAPITULO	RESUMEN	EUROS	%
C01	ACTUACIONES PREVIAS.....	47.649,45	8,67
C02	ESTRUCTURA.....	89.368,41	16,26
C03	CUBIERTA.....	33.745,31	6,14
C04	FACHADA.....	74.208,28	13,50
C05	PARTICIONES.....	80.150,35	14,59
C06	REVESTIMIENTOS.....	64.585,00	11,75
C07	INSTALACIONES.....	129.618,27	23,59
C08	PINTURAS.....	19.900,71	3,62
C09	SEGURIDAD Y SALUD.....	4.170,91	0,76
C10	CONTROL DE CALIDAD.....	1.432,39	0,26
C11	GESTIÓN DE RESIDUOS.....	4.693,99	0,85
TOTAL EJECUCIÓN MATERIAL		549.523,07	
21,00% IVA.....		115.399,84	
TOTAL CERTIFICACIÓN N°		664.922,91	

So the construction cost per usable square meter was: $549.523,07 \text{ €} / (237,9+334,0) \text{ m}^2 = 960,87 \text{ €/m}^2$

12. Other information

The house was built along the 2015 and 2016 years, and it was finished in April 2016.

The architects of the building were BOA arquitectos (Raúl Belloso Luqui, Pablo Díaz Torquemada and Iñaki archanco Mancho).

The structure of the building is formed with concrete pillar and beams supporting concrete slabs. The foundation of the building is a concrete slab. The isolation goes under the foundation slab.

12.1 Experiences

The houses were designed and built for the use of tourist groups to spend short periods of time so they could experience a passivhaus.

The houses have been open from June 2016.

The occupation level of the houses has not been very high, but the satisfaction degree of the occupants was high, and the inside temperatures, both in summer and winter were good, except during the summer of 2016. In that period the temperatures inside were high because the night free-cooling with the opening of the windows was not done (during that period there were not users).

For the summer of 2017 exterior wood blinds were placed in the south windows of the north house:



This was enough to keep a low temperature inside the houses even though they were not occupied so windows were not opened during night time to do the free-cooling.

The houses have a home automation system to control the air exchanging device and the air to water pump for the hot water production. This system keeps information on temperatures, electricity consumption,...


The electricity consumption of the air bomb (for hot water production) during one year was:



The reference surface of the house is 203,3 m². So the annual consumption for square meter was:

$$3.229 \text{ kWh} / 203,3 \text{ m}^2 = 15,88 \text{ kWh} / \text{m}^2 \text{ per year}$$

The total electricity consumption during one year was



The reference surface of the house is 203,3 m². So the annual consumption for square meter was:

$$5.818 \text{ kWh} / 203,3 \text{ m}^2 = 28,61 \text{ kWh} / \text{m}^2 \text{ per year}$$