

HOUSE WITH WINTER GARDEN

Project Documentation



**New built detached single family house,
constructed in 2016 in Dabrowa Chotomowska, Poland**

1. Abstract

Year of construction	2016	Space Heating	15 kWh/(m²a)
U-value external wall	0.083 W/(m²K)		
U-value base-ment ceiling	0.111 W/(m²K)	Primary Energy Renewable (PER)	25 kWh/(m²a)
U-value roof	0.073 W/(m²K)	Generation of renewable energy	65 kWh/(m²a)
U-value window	0.80 W/(m²K)	Non-renewable Primary Energy (PE)	53 kWh/(m²a)
Heat recovery	81,8%	Pressure test n50 /	0.22/h
Special features	Photovoltaic instalation 10 kWp, First polish Passive House Plus.		

1.1. Brief description

The house is designed to maximize the comfort of living. The highlight of the project is a south-facing winter garden that is an extension of the living room. Winter garden connects the interior of the house with its exterior creating a natural buffer zone, where the whole family can experience nature in any weather conditions. The House with Winter Garden is the first Polish building being certified in the Passive House Plus standard.

The building is designed for a family of four. The functional layout is as follows: the living room, dining room, and kitchen are located on the ground floor on the south side of the building. Along the north facade, there is a bathroom with a sauna, technical room and home office (with windows facing east). Master bedroom, children's bedrooms, and two additional bathrooms are located on the first floor.

The timber-frame building is constructed using the I-joist system to reduce thermal bridges.

1.3 Responsible project participants

Architecture and building physics: Pasywny M2, Agnieszka Figielek

Building services

MVHR design and supply: BR Engineers, Bartosz Radomski

Renewables: Solar array, Immersun units and electrics: Bison Energy

Structural engineer: Roman Pilch

Craftsperson / parties involved:

Bartosz Królczyk - advisor

Certifying body: Passivhaus Institut, Darmstadt

Certification ID: 6282 (Passive House Database)

2. Views of the building



View of the west facade



View of the south facade



View of the building during construction period



View of the north facade




View of the south facade



View of the winter garden


3. Sectional drawings




Cross section running from North to South via winter garden




Cross section running from North to South shown in perspective




Cross section running from East to West




Foundation slab



Window-slab connection



Ground floor plan



First floor plan

Ground floor:

The open-plan living room connected with dining room and kitchen are located on the south facade of the building. Service room and the bathroom are located on the north facade and act as a thermal buffer.

First floor:

The functional layout of the first floor also reflects the idea of thermal zoning. Large, south facade glazing contrast with small windows on the northern side.

5. Construction

5.1. Ground floor

Basement floor / floor slab



-300 mm insulation XPS

-250 mm reinforced concrete slab

U-value = 0.111 W/(m²K)

Foundation slab was highly insulated with polystyrane.

What is more, wall foundation was divided into two parts in order to eliminate thermal bridges.





5.2. External wall

Layers:

- 10 mm plaster
- 40 mm wood fiber wool
- 500 mm wood fiber wool/I-studs
- 18 mm OSB
- 15 mm plasterboard

U-value = 0.083 W/(m²K)

Construction materials are made from renewable material -wood. I-studes are manufactured and join in the prefabricated wall elements in the nearby factory and then transported to the building site.




5.3. Roof

Layers:

- roof tile
- 40 mm wood fiber wool
- 300 mm wood fiber wool/ scantling
- 18 mm OSB
- 200 mm wood fiber wool/ I-studs
- 13 mm plasterboard

Roof was constructed using prefabricated I-studs, with insulation - both between the studs and on the top of them.




5.4. Windows

Layers:

- 10 mm plaster
- 40 mm wood fiber wool
- 500 mm wood fiber wool/I-studs
- 18 mm OSB
- 15 mm plasterboard

U-value = 0.083 W/(m²K)

High quality windows were used in the project - Energeto 8000 I passiv; CI-System with Vinyl window frame, insulated by PU-foam (0,030 W/(mK)), reinforced by Polyamide with 25% glassfibre (0,30 W/(mK)).



6. Air tightness

The airtightness strategy was to ensure a single layer of airtightness by the use of tapes, grommets and fittings. OSB board were used as airtight layer, all joints and penetrations were sealed with tapes.

Care was taken to protect this during the casting and polishing of the concrete slab.

The windows were installed in an exterior subframe, with all connections between sheathing, subframe, and window frame being sealed with tape.



Certificate

about the BlowerDoor Test

Object:

**Budynek jednorodzinny
ul.Modrzewiowa 22
Dąbrowa Chotomowska
05-123 Dąbrowa Chotomowska**

Test Date: 12.08.2016

Air change rate (n50) at 50 Pascal
according to EN 13829, Method A

n50 = 0,22 1/h

Regulation complied with: PN_EN 13829

n50 ≤ 0,6 1/h

The test results meet the regulation.

2016-08-21

Katarzyna Jarocka

PASS Doradztwo Energetyczne Tęczowa 9, Góra
Tarnowo Podgórne
tel. 795 435 837

BlowerDoor Test

EN 13829, Method A

Building Test Info and Air-Moving Equipment

Building Information

Building:	Budynek jednorodzinny ul. Modrzewiowa 22
Address:	Dąbrowa Chotomowska 05-123 Dąbrowa Chotomowska
	Year of Construction: 2016
	Test Date: 12.08.2016

Customer Information

Name:	Przemysław Romaniuk
Address:	ul. Czarneckiego 71 05-120 Legionowo
Phone:	
Fax:	

Business Info

Name: PASS Doradztwo Energetyczne Tęczowa 9, Góra	Technician: Katarzyna Jarocka
Address: Tarnowo Podgórne tel. 795 435 837	Phone: 795 435 837
	Fax:

Test Method

Method:	A Test of a building in use
Standard:	Following EN 13829
Note:	

Test object:

Test object:	Budynek konstrukcji szkieletowej [system Steico], posadowiony na płycie fundamentowej.		
Internal Volume V:	662 m ³	Error: +/- 5 %	Calculation Reference Values:
Net Floor Area A _F :	214 m ²		see appendix
Envelope Area A _E :	495 m ²		
Type of Ventilation:	☒ Yes ☐ mechaniczna z odzyskiem		
Type of Heating System:	pompa ciepła/ogniwa PV		
Type of Air Conditioning:	pasywne chłodzenie - pompa ciepła		
Additional Information you will find in "Comments".			

Air-moving Equipment

Device:	Minneapolis BlowerDoor Modell 4, APT		
Serial Numbers:	Fan: CE 2880	Pressure Gauge: DG-700	Calibration:
Other Devices:			

BlowerDoor Test

Test Standard EN 13829, Method A

Minneapolis BlowerDoor Modell 4 - Tectite Express 3.6.7.0

Object: <u>Budynek jednorodzinny ul.Modrzewiowa 22</u> <u>05-123 Dąbrowa Chotomowska</u>	Technician: <u>Katarzyna Jarocka</u> Date: <u>12.08.2016</u>
---	---

Temperature and Wind Conditions

Inside Temperature: <u>20 °C</u>	Wind Force: <u>2</u>
Outside Temperature: <u>18 °C</u>	Number of exterior pressure taps: <u>1</u>
Barometric Pressure: (Standard): <u>101325 Pa</u>	Building Wind Exposure: <u>B</u>
Uncertainty because of Wind (Table Geißler): 2 %	

Depressurization

Zero Flow	Δp_{01+}	Δp_{01-}	Δp_{02+}	Δp_{02-}
(baseline)	-	-0,2 Pa	0,8 Pa	-0,6 Pa

Pressurization

Zero Flow	Δp_{01+}	Δp_{01-}	Δp_{02+}	Δp_{02-}
(baseline)	0,1 Pa	-0,1 Pa	0,1 Pa	-0,1 Pa

Sets of Measurement

Ring	Building Pressure	Fan Pressure	Fan Flow V_f	Tolerance	Ring	Building Pressure	Fan Pressure	Fan Flow V_f	Tolerance
O ABCDE	[Pa]	[Pa]	[m³/h]	[%]	O ABCDE	[Pa]	[Pa]	[m³/h]	[%]
Δp_{01}	-0,2	—	—	—	Δp_{01}	0,0	—	—	—
C	-69	81	187	-0,35	C	67	77	181	-0,07
C	-65	73	177	-0,18	C	65	74	177	1,19
C	-60	65	167	0,79	C	59	62	163	0,01
C	-54	55	152	-0,39	C	54	53	150	-0,66
C	-49	47	141	-0,04	C	49	45	137	-1,33
C	-44	40	130	-0,03	C	43	39	128	0,45
C	-41	35	121	0,93	C	40	34	120	0,75
C	-34	26	103	-0,91	C	34	26	103	-0,58
C	-30	21	93	0,10	C	29	21	92	-0,44
D	-27	47	85	0,10	C	24	16	80	0,71
Δp_{02}	-0,5	—	—	—	Δp_{02}	-0,1	—	—	—

Correlation Coefficient r:		Confidence interval		Correlation Coefficient r:		Confidence interval	
C_{env}	[m³/(h Paⁿ)]	6	max. 6 min. 5	C_{env}	[m³/(h Paⁿ)]	6	max. 7 min. 6
C_L	[m³/(h Paⁿ)]	6	max. 6 min. 5	C_L	[m³/(h Paⁿ)]	6	max. 7 min. 6
n	[-]	0,82	max. 0,83 min. 0,81	n	[-]	0,81	max. 0,82 min. 0,79

Results

V =		662 m³	A _F =		214 m²	A _E =		495 m²
	V ₅₀	Uncertainty	n ₅₀	Uncertainty	w ₅₀	Uncertainty	q ₅₀	Uncertainty
	m³/h	%	1/h	%	m³/m²h	%	m³/m²h	%
Depressurisation	143	+/- 7 %	0,22	+/- 9 %	0,67	+/- 9 %	0,29	+/- 9 %
Pressurisation	143	+/- 7 %	0,22	+/- 9 %	0,67	+/- 9 %	0,29	+/- 9 %
Average	143	+/- 7 %	0,22	+/- 9 %	0,67	+/- 9 %	0,29	+/- 9 %

Regulation complied with:

PN EN 13829

Maximum allowable:

0,6	1/h				
------------	-----	--	--	--	--

The test results meet the regulation.

Note: The result does not exclude faults in the construction.

Business Info: Katarzyna Jarocka


PASS Doradztwo Energetyczne Tęczowa 9, Góra

tel. 795 435 837

Date, Sign

Stamp

BlowerDoor Air Leakage Graph
Object: Budynek jednorodzinny ul.Modrzewiowa 22



- ◆ (Air Flow) Depressurisation [m^3/h]
- (Air Flow) Pressurisation [m^3/h]
- Regression line Depressurisation [m^3/h]
- - - Regression line Pressurisation [m^3/h]
- × Air Flow Rate at 50 Pa [m^3/h]

BlowerDoor Test

EN 13829, Method A

Zero-Flow (Baseline) and Accuracy

Object:	Budynek jednorodzinny ul.Modrzewiowa 22 05-123 Dąbrowa Chotomowska	Technician: Katarzyna Jarocka
Date:	12.08.2016	

Depressurization

Reading	Zero Flow Pressure Difference	
	At the Beginning	At the End
1	-0,3	-1,1
2	-0,3	-0,3
3	-0,3	-0,3
4	-0,3	-0,8
5	-0,3	-1,1
6	-0,3	-0,3
7	-0,3	-0,4
8	-0,3	-0,4
9	-0,3	-0,8
10	-0,3	0,3
11	-0,2	1,3
12	-0,3	-0,4
13	-0,2	-0,5
14	-0,2	-0,5
15	-0,3	-0,5
16	-0,2	-0,5
17	-0,2	-0,5
18	-0,2	-0,6
19	-0,2	-0,6
20	-0,2	-0,6
21	-0,2	-0,6
22	-0,1	-0,7
23	-0,1	-0,6
24	-0,1	-0,7
25	-0,1	-0,7
26	-0,2	-0,8
27	-0,1	-0,8
28	-0,2	-0,9
29	-0,1	-0,9
30	-0,2	-0,9

Pressurization

Reading	Zero Flow Pressure Difference	
	At the Beginning	At the End
1	0,0	0,2
2	0,0	0,2
3	0,0	0,1
4	0,0	0,1
5	0,1	0,1
6	0,1	0,0
7	0,1	0,0
8	0,1	0,0
9	0,1	0,0
10	0,1	0,0
11	0,2	0,0
12	0,2	0,0
13	0,1	-0,1
14	0,1	-0,1
15	0,1	-0,1
16	0,1	-0,1
17	0,1	-0,1
18	0,1	-0,1
19	0,1	-0,1
20	0,1	-0,1
21	0,0	-0,1
22	0,0	-0,1
23	0,0	-0,1
24	0,0	-0,1
25	-0,1	-0,1
26	-0,1	-0,1
27	-0,1	-0,2
28	-0,2	-0,2
29	-0,2	-0,1
30	-0,1	-0,1

Average of the positive and negative Values of Zero Flow Pressure Difference

	Δp_{01+}	Δp_{01-}	Δp_{02+}	Δp_{02-}		Δp_{01+}	Δp_{01-}	Δp_{02+}	Δp_{02-}
Average	-	-0,2	0,8	-0,6	Average	0,1	-0,1	0,1	-0,1

Average of all Values of Zero Flow Pressure Difference

Zero Flow	Δp_{01} [Pa]	Δp_{02} [Pa]	Zero Flow	Δp_{01} [Pa]	Δp_{02} [Pa]
(baseline)	-0,2	-0,5	(baseline)	0,0	-0,1


Note:

Accuracy (Proposal Germany: FLiB-Supplement 11/2001)

Name	Description	Depressurisation		Pressurisation	
a	Accuracy of the device to measure airflow rate	+/- 4 %		+/- 4 %	
b	Accuracy building pressure	+/- 3 %	50 Pa	+/- 3 %	50 Pa
c	Uncertainty because of wind	+/- 2 %		+/- 2 %	
d	Uncertainty barometric pressure (standard or measured)	+/- 5 %		+/- 5 %	
e	Uncertainty leaving out a depressurization or pressurization	+/- 0 %		+/- 0 %	
g	Uncertainty reference values	+/- 5 %		+/- 5 %	
only info	Random error of the airflow rate	+/- 0 %		+/- 1 %	


7. Ventilation system

Design of the ventilation system was carried out by Bartosz Radomski, certified Passive House service designer. He used a Paul Novus (F) 300 unit. The MVHR unit has an effective heat recovery performance of 81,8%.



Ground floor - ductwork layout.

Supply air ductwork shown in blue Extract ductwork shown in red




First floor - ductwork layout.

Supply air ductwork shown in blue Extract ductwork shown in red


8. Heating system

As a passive house, the building requires minimal amount of energy for heating. The heating system and water heating supply is provided by air source heat pump with internal storage tank. The device is Waterkotte, Basic Line Ai1 Air. COP=3,7.

Ground floor - floor
heating layout



First floor - floor
heating layout





Service room

Heating system



9. PHPP verification

budynek pasywny-Ocena																																																																																													
				obiekt: Budynek jednorodzinny z wiatą ulica: Modrzewiowa kod pocztowy / miejscowość: 05-123 Dąbrowa Chotomowska provincia / kraj: Polska PL-Polska typ obiektu: budynek jednorodzinny dane klimatyczne: PL0003a-Warszawa strefa klimatyczna: 2: zimny wysokość standardowa: 78,52 m																																																																																									
				inwestor: Anna Jakubowska Romaniuk i Przemysław Romaniuk ulica: Czarnieckiego 71 kod pocztowy / miejscowość: 05-120 Legionowo provincia / kraj: Polska																																																																																									
				biuro projektowe: BR Engineers Bartosz Radomski ulica: Krańcowa 62/27 kod pocztowy / miejscowość: 61-036 Poznań provincia / kraj: Polska																																																																																									
				architektura: Pasywny M2 Agnieszka Figielek ulica: Janusza Zeylanda 6/11 kod pocztowy / miejscowość: 60-366 Poznań provincia / kraj: Polska																																																																																									
				doradztwo energetyczne: Bartosz Królczyk ulica: Szydłowska 3/36 kod pocztowy / miejscowość: 60-651 Poznań provincia / kraj: Polska																																																																																									
rok budowy: 2016 ilość mieszkań: 1 ilość osób: 3,1				temperatura wewnętrzna zimą [°C]: 20,0 wewnętrzne źródła ciepła (WZC) ogrzewanie [W/m²]: 2,3 char. pojemność [Wh/K na m² UPO]: 60		temp. wewnętrzna latem [°C]: 25,0 WZC chłodzenie [W/m²]: 2,3 chłodzenie mechaniczne																																																																																							
Wskaźniki budynku odniesione do umownej powierzchni ogrzewanej na rok																																																																																													
<table border="1"> <thead> <tr> <th colspan="2">Umowna powierzchnia ogrzewana m²</th> <th></th> <th colspan="2">kryteria</th> <th colspan="2">kryteria alternatywne</th> <th colspan="2">spełnione?²</th> </tr> </thead> <tbody> <tr> <td rowspan="2">ogrzewanie</td> <td>zapotrzebowanie na ciepło do ogrzewania kWh/(m²a)</td> <td>209,4</td> <td>≤</td> <td>15</td> <td>-</td> <td></td> <td>tak</td> </tr> <tr> <td>obciążenie ogrzewcze W/m²</td> <td>13</td> <td>≤</td> <td>-</td> <td>10</td> <td></td> <td></td> </tr> <tr> <td rowspan="3">obciążenie ogrzewcze</td> <td>chłodzenie + zapotrzebowanie na osuszanie kWh/(m²a)</td> <td>-</td> <td>≤</td> <td>-</td> <td>-</td> <td></td> <td>-</td> </tr> <tr> <td>obciążenie chłodnicze W/m²</td> <td>-</td> <td>≤</td> <td>-</td> <td>-</td> <td></td> <td></td> </tr> <tr> <td>częstotliwość przegrzewania (> 25 °C) %</td> <td>2</td> <td>≤</td> <td>10</td> <td></td> <td></td> <td>tak</td> </tr> <tr> <td></td> <td>częstość podwyższonej wilgotności (> 12 g/kg) %</td> <td>0</td> <td>≤</td> <td>20</td> <td></td> <td></td> <td>tak</td> </tr> <tr> <td>szczelność powietrzna</td> <td>wymiana powietrza podczas próby ciśn. n50 1/h</td> <td>0,2</td> <td>≤</td> <td>0,6</td> <td></td> <td></td> <td>tak</td> </tr> <tr> <td>nieodnawialna energia pierwotna (EP)</td> <td>zapotrzebowanie EP kWh/(m²a)</td> <td>53</td> <td>≤</td> <td>-</td> <td></td> <td></td> <td>-</td> </tr> <tr> <td rowspan="2">odnawialna energia pierwotna (PER)</td> <td>zapotrzebowanie PER kWh/(m²a)</td> <td>25</td> <td>≤</td> <td>45</td> <td>30</td> <td></td> <td rowspan="2">tak</td> </tr> <tr> <td>wytworzenie odnawialnej energii (na powierzchnię nadbudowy) kWh/(m²a)</td> <td>65</td> <td>≥</td> <td>60</td> <td>39</td> <td></td> </tr> </tbody> </table>										Umowna powierzchnia ogrzewana m²			kryteria		kryteria alternatywne		spełnione? ²		ogrzewanie	zapotrzebowanie na ciepło do ogrzewania kWh/(m²a)	209,4	≤	15	-		tak	obciążenie ogrzewcze W/m²	13	≤	-	10			obciążenie ogrzewcze	chłodzenie + zapotrzebowanie na osuszanie kWh/(m²a)	-	≤	-	-		-	obciążenie chłodnicze W/m²	-	≤	-	-			częstotliwość przegrzewania (> 25 °C) %	2	≤	10			tak		częstość podwyższonej wilgotności (> 12 g/kg) %	0	≤	20			tak	szczelność powietrzna	wymiana powietrza podczas próby ciśn. n50 1/h	0,2	≤	0,6			tak	nieodnawialna energia pierwotna (EP)	zapotrzebowanie EP kWh/(m²a)	53	≤	-			-	odnawialna energia pierwotna (PER)	zapotrzebowanie PER kWh/(m²a)	25	≤	45	30		tak	wytworzenie odnawialnej energii (na powierzchnię nadbudowy) kWh/(m²a)	65	≥	60	39	
Umowna powierzchnia ogrzewana m²			kryteria		kryteria alternatywne		spełnione? ²																																																																																						
ogrzewanie	zapotrzebowanie na ciepło do ogrzewania kWh/(m²a)	209,4	≤	15	-		tak																																																																																						
	obciążenie ogrzewcze W/m²	13	≤	-	10																																																																																								
obciążenie ogrzewcze	chłodzenie + zapotrzebowanie na osuszanie kWh/(m²a)	-	≤	-	-		-																																																																																						
	obciążenie chłodnicze W/m²	-	≤	-	-																																																																																								
	częstotliwość przegrzewania (> 25 °C) %	2	≤	10			tak																																																																																						
	częstość podwyższonej wilgotności (> 12 g/kg) %	0	≤	20			tak																																																																																						
szczelność powietrzna	wymiana powietrza podczas próby ciśn. n50 1/h	0,2	≤	0,6			tak																																																																																						
nieodnawialna energia pierwotna (EP)	zapotrzebowanie EP kWh/(m²a)	53	≤	-			-																																																																																						
odnawialna energia pierwotna (PER)	zapotrzebowanie PER kWh/(m²a)	25	≤	45	30		tak																																																																																						
	wytworzenie odnawialnej energii (na powierzchnię nadbudowy) kWh/(m²a)	65	≥	60	39																																																																																								
² puste pole: brak danych; '-': brak wymagań																																																																																													
Zapewniam, że wprowadzono tutaj wartości zgodnie z metodą PHPP na podstawie wskaźników budynku. Obliczenia PHPP są dołączone do Oceny.																																																																																													
funkcja: 2-certyfikowany				imię:		nazwisko:		budynek pasywny Plus? tak																																																																																					
wystawiono:				miejscowość:		podpis:																																																																																							

Energy balance - heating (annual method)

