

## Project Documentation

### Abstract



Single storey (plus mezzanine) detached holiday home on banks of Ullswater, Lake District, UK

### Building data

Year of construction	2021
U-value-wall	0.089 W/m <sup>2</sup> K
U-value-ground slab	0.100 W/m <sup>2</sup> K
U-value-roof	0.089 W/m <sup>2</sup> K
U-value-window (average)	0.84 W/m <sup>2</sup> K
Heat recovery	90%
Space heating demand	14.2 kWh/m <sup>2</sup> a
Primary Energy Renewable (PER)	54 kWh/m <sup>2</sup> a
Generation of renewable energy	25 kWh/m <sup>2</sup> a
Non-renewable primary energy	108 kWh/m <sup>2</sup> a
Pressure test n <sub>50</sub>	0.14 h <sup>-1</sup> @ 50Pa.

### Brief description

Tether is built as a private holiday home for the architect owners who live and work in Stockport, Greater Manchester. It replaces an existing 1950s bungalow which had reached end of life; the bungalow benefitted from an enviable location and view of Ullswater and was offered for sale on the open market in 2019. Discussions were held with the Lake District National Park planning authority who agreed in principle to replacement of the bungalow with a new dwelling having similar form and materials. During 2020 the design evolved and planning permission obtained without challenge; construction started at the beginning of January 2021.

The passivhaus envelope is a simple rectangular form with a cathedral roof extending for its full 14m length. The open plan lounge, dining and kitchen occupy the southern half of the home. The north half contains bedrooms and bathrooms, with a mezzanine structure above offering reduced height accommodation and the plant room. This additional floor area did improve the form factor but it remains poor at 3.9 owing to the building's relatively small size.

The primary views, and large windows therefore, are to the south-west and west. The south facing gable end looks onto a wooded area. Outriggers extend at each corner to support the hidden gutter and eaves structure on either long side; this structure also provides solar shading to the glazed areas.

Once the groundworks and insulated raft foundation were complete, construction was swift. The prefabricated timber frame panels were installed within three days, with the windows and external doors following soon after providing a fully air and weathertight envelope. The project was completed within six months of clearing the site.

### Project participants

Architect: Hesketh Hayden  
[www.heskethhayden.co.uk](http://www.heskethhayden.co.uk)  
Project management: Hesketh Hayden  
Energy consultants: Hesketh Hayden and Humblebee Eco  
[www.humblebee.co.uk](http://www.humblebee.co.uk)  
Mechanical services: Humblebee Eco  
Structural engineering: via Eden Insulation  
[www.edeninsulation.co.uk](http://www.edeninsulation.co.uk)  
Certifier: Etude  
[www.etude.co.uk](http://www.etude.co.uk)


Certification ID 7086

### Author of project documentation

Hesketh Hayden

Date: 01 December 2022

Signature:



Location plan

## Views of completed building



*View from north*




*View from north-west*




*View from south*




*Interior views*



## Section drawings



## Floor plans





## Description of the construction


### 1. Ground floor slab

The reinforced concrete slab is 260mm thick and sits inside a 300mm thick EPS insulation 'tray'. The concrete has 50% GGBS cement replacement.

Assembly no.	Building assembly description				Interior insulation?
01ud	Floor slab				
Orientation of building element: 3-Floor		Heat transmission resistance [m <sup>2</sup> KW]			
Adjacent to: 2-Ground		interior R <sub>si</sub> : 0.17			
		exterior R <sub>se</sub> : 0.00			
Area section 1	λ [W/(mK)]	Area section 2 (optional)	λ [W/(mK)]	Area section 3 (optional)	λ [W/(mK)]
Porcelain tile	1.500				
Concrete slab	2.100				
Insulation-Isoquick	0.031				
Percentage of sec. 1: 100%		Percentage of sec. 2:		Percentage of sec. 3:	
U-value supplement: W/(m <sup>2</sup> K)		U-value: 0.100 W/(m <sup>2</sup> K)			
				Total Thickness [mm]: 57.5 cm	



EPS insulation tray being installed



Isotherm diagram of wall/floor junction

### 2. External walls and roof

The wall and roof superstructure comprises prefabricated panels, assembled locally with 400mm deep engineered timber I-joists, cellulose insulation fill, 22mm woodfibre sarking externally and 12mm Propassiv OSB internally. A single 14m long glulam ridge beam spans the length of the building providing support to the roof panels. After taping and sealing, the frame was fully weathertight within three days of starting.


Assembly no.	Building assembly description				Interior insulation?
04.80952380952381ud	Wall above ground				
Orientation of building element: 2-Wall		Heat transmission resistance [m <sup>2</sup> KW]			
Adjacent to: 1-Outdoor air		interior R <sub>si</sub> : 0.13			
		exterior R <sub>se</sub> : 0.04			
Area section 1	λ [W/(mK)]	Area section 2 (optional)	λ [W/(mK)]	Area section 3 (optional)	λ [W/(mK)]
Plasterboard	0.250				
Service void-Th'fleece	0.039				
Chipboard-VapourBlock	0.130				
Insulation-Isofloc blown	0.038	timber battens	0.130	timber battens	0.130
Insulation-Isofloc blown	0.038			timber battens	0.130
Insulation-Isofloc blown	0.038	timber battens	0.130	timber battens	0.130
Insulation-Multiplex Top	0.044				
Percentage of sec. 1: 79%		Percentage of sec. 2: 16.5%		Percentage of sec. 3: 4.5%	
U-value supplement: W/(m <sup>2</sup> K)		U-value: 0.089 W/(m <sup>2</sup> K)			
				Total Thickness [mm]: 49.5 cm	



*Prefabricated wall panels being craned into position*



*Installation of prefabricated first floor panels towards end of Day 1*



*View of completed frame from mezzanine*


The outrigger structure on each long side is outside and structurally independent from the passivhaus thermal envelope. Deep LVL beams span between the external storage volumes at each corner.

External walls are boarded and finished with render. Solid wall surfaces below the overhangs are clad with narrow vertical larch boards, pre-finished with SiOOX weather treatment to maintain an even appearance.

The roof re-uses the Westmoreland slates from the previous dwelling, falling to deep hidden gutters that drain at each end to outlets and downpipes within the corner outriggers. The south-west facing roof has photovoltaic panels, detailed to sit flush with the adjacent slates, and two quadruple glazed rooflights providing daylight at mezzanine level.



View of hidden gutter




Detail section at eaves through hidden gutter and outrigger

### 3. Windows

Window openings are formed within the prefabricated structural wall panels with double or triple I-joists at the jambs and LVL lintels above.

Airtightness is achieved with internal and external tape, expanding foam tape was applied to the perimeter just before windows were positioned. Heat was applied at some corners to ensure the expanding tape fully filled the gaps.

- 1 Engineered I-joists full filled with cellulose insulation
- 5 22mm woodfibre sarking insulation
- 8 Idealcombi Futura+i inward opening window frame
- 9 site fixed timber packer
- 10 Tescon Profil internal airtightness tape
- 11 galv. steel window fixing strap
- 12 Tescon Vana external airtightness tape
- 13 expanding foam tape
- 19 12mm render carrier board
- 20 25mm treated battens
- 21 render system with mesh reinforcement
- 22 window cill below.



Typical window jamb detail in rendered wall



#### 4. Airtight envelope

The prefabricated wall and roof panels arrived on site fully sealed and airtight. All panels are lined internally with 12mm *Propassiv* structural OSB boards, simply butt jointed, then taped internally and externally with *Tescon Vana No.1* tape. The junction between panels and concrete floor slab are sealed with brush applied *Aerosana Visconn* liquid membrane. Airtightness at ground level relies on the concrete raft.




Construction view of prefabricated external wall and floor panels



Testing in progress

Air leakage was measured by Green Footsteps by blower door test based on the building volume of 363m<sup>3</sup>. The interim and final tests achieved an average air change per hour ( $n_{50}$ ) of 0.14 h<sup>-1</sup> @ 50Pa.

The quadruple glazed *Fakro* rooflights were seen to be the most problematic in not achieving better airtightness, with air leakage evident between frames using infrared imagery and smoke during depressurisation. *Fakro* were invited to comment on the poor performance but they considered them to be within the specified parameters and offered no further assistance.



Infrared image of rooflight during airtightness test



Smoke testing during airtightness test



## 5. Ventilation system

The unit chosen for the mechanical ventilation system is Systemair's SAVE VTC 200R. It is located at mezzanine level within the dedicated plantroom space, entirely within the thermal envelope. The unit is certified to provide an air recovery rate of 90%.

The unit is against the external wall with short duct lengths (approx. 300mm) to the external wall, insulated with Armaflex insulation. Galvanised spiral metal ductwork extends from the unit within the first floor void to the bedrooms and wet rooms below and to the main living space. In-line silencers are concealed within the floor void and within the plantroom.




Systemair SAVE VTC 200R unit installed in plant room



Ductwork and silencers located in first floor void

The Systemair unit has a large hinged front panel for maintenance and filter change. The panel is, however, secured with eight specialist head screws, making access time consuming and fiddly.



First floor plan with MVHR system located in plant room and first floor void

## 6. Heat supply system and hot water

The strategy for space heating at Tethera is simple. It relies on good solar gains through the substantial glazed areas to the south and west, gains from human activity, and output from two electric towel rails, one in the Bathroom and one in the Shower. These are Rointe D-Series 600W units with built-in WiFi for remote control. There are no other dedicated heat sources.


Domestic hot water is provided by a Mixergy electric immersion hot water storage tank located in the plantroom. The 150L Direct Smart Cylinder links to the 12-panel photovoltaic array via a diverter and has primary and backup electric immersion heaters.

The cylinder's hot water draw pipe is connected to a 32mm steel manifold with six connections. The hot water temperature in the distribution pipework is maintained by ensuring short runs from the distribution manifold in 8mm PEX pipework direct to fittings.

A GivEnergy battery is installed with a capacity of 8.2kWh, allowing greater use of on-site generated electricity. The solar PV system is set up to meet in-house electricity demands first, followed by water heating and then battery storage.



*Hot water manifold system*



*Insulated 8mm PEX pipework*

PHPP calculations

**Architecture:** Hesketh Hayden  
Street: 2 Churwell Avenue  
Postcode/City: SK4 3QE Stockport  
Province/Country: Greater Manchester UK

**Energy consultancy:** Humblebee Eco  
Street: Hawthorn Walk  
Postcode/City: SK9 5BS  
Province/Country: Cheshire

Year of construction: 2021  
No. of dwelling units: 1  
No. of occupants: 2.5

**Building:** Tethera  
Street: Watermilllock  
Postcode/City: CA110JN Penrith  
Province/Country: Cumbria GB-United Kingdom/Britain  
Building type: Single family home  
Climate data set: GB0009a-Carlisle  
Climate zone: 3: Cool-temperate Altitude of location: 170 m

**Home owner / Client:** Russel Hayden  
Street: 2 Churwell Avenue  
Postcode/City: SK4 3QE Stockport  
Province/Country: Greater Manchester

**Mechanical system:** Humblebee Eco  
Street: Hawthorn Walk  
Postcode/City: SK9 5BS  
Province/Country: Cheshire

**Certification:**  
Street:  
Postcode/City:  
Province/Country:

Interior temperature winter [°C]: 20.0  
Interior temp. summer [°C]: 25.0  
Internal heat gains (IHG) heating case [W/m²]: 2.6  
IHG cooling case [W/m²]: 2.6  
Specific capacity [Wh/K per m² TFA]: 84  
Mechanical cooling:

**Specific building characteristics with reference to the treated floor area**

	Treated floor area m²		Criteria	Alternative criteria	Fulfilled? <sup>2</sup>
Space heating	Heating demand kWh/(m²a)	14.2	≤ 15	-	yes
	Heating load W/m²	10	≤ -	10	yes
Space cooling	Cooling & dehum. demand kWh/(m²a)	-	≤ -	-	-
	Cooling load W/m²	-	≤ -	-	-
	Frequency of overheating (> 25 °C) %	0	≤ 10	-	yes
	Frequency excessively high humidity (> 12 g/kg) %	0	≤ 20	-	yes
Airtightness	Pressurization test result n <sub>50</sub> 1/h	0.1	≤ 0.6	-	yes
Non-renewable Primary Energy (PE)	PE demand kWh/(m²a)	108	≤ -	-	-
Primary Energy Renewable (PER)	PER demand kWh/(m²a)	54	≤ 60	60	yes
	Generation of renewable energy kWh/(m²a)	25	≥ -	-	-


<sup>2</sup> Empty field: Data missing; "-": No requirement

I confirm that the values given herein have been determined following the PHPP methodology and based on the characteristic values of the building. The PHPP calculations are attached to this verification.

Task: First name: russel Surname: hayden  
Issued on: City:

Passive House Classic? yes  
Signature:

Energy balance heating (annual method)





Extracts taken from PHPP spreadsheet



## Embodied carbon and operational energy

Calculations have been carried out by Tim Martel to assess the embodied carbon for the proposals. The as-built home scored a cradle-to-grave embodied carbon figure of **351kg CO<sub>2</sub>e/m<sup>2</sup> GIA**, satisfying the RIBA 2030 Climate Challenge target. The concrete slab is a major limiting factor to a better result, despite adopting 50% GGBS as cement replacement.

The operational energy figure is **39kWh/m<sup>2</sup>.a** GIA, satisfying the RIBA 2025 Climate Challenge target.



if Operational varies then adjust these cells				
Operational	Option 1	Option 2	Option 3	Option 4
Space Heating kWh/m <sup>2</sup> .a	14.2	14.2	14.2	14.2
Final Energy kWh/m <sup>2</sup> .a (excl PV)	41.6	41.6	41.6	41.6
Tonnes CO <sub>2</sub> e over 60yrs (incl PV)	3.5	0.0	0.0	0.0
kgCO <sub>2</sub> e/m <sup>2</sup> GIA over 60yrs (incl PV)	29.4			

Embodied	Option 1	Option 2	Option 3	Option 4
tonnes CO <sub>2</sub> e A-C over 60yrs	41.4	0.0	0.0	0.0
RIBA kgCO <sub>2</sub> e/m <sup>2</sup> GIA over 60yrs	351.2			
LETI kgCO <sub>2</sub> e/m <sup>2</sup> GIA over 60yrs	268.7			

		Option 1 Embodied CO <sub>2</sub> kgCO <sub>2</sub> e/M <sup>2</sup> GIA									
Building element category		A1-A3 Manufac	A1-A3 Sequestered	A4 Transp to site	A5 Construc	B1, B2, B3	B4, B5	C1-4	D		
Facilitating works	Toxic Material Treatment								0	0	0
	Major Demolition Works								0	0	0
	Temporary Enabling Works	0	0	0		0	0	0	0	0	0
	Specialist Ground works	0	0	0		0	0	0	0	0	0
	Substructure	90	0	11		0	6	11	5		
Superstructure	Frame	0	0	0		0	0	0	0		
	Upper floors incl. balconies	5	-14	0		0	0	0	15	0	
	Roof	20	-76	4		0	0	56	-19		
	Stairs and ramps	0	0	0		0	0	0	0		
	External Walls	34	-118	7		0	6	85	-36		
	Windows and External Doors	19	0	2		0	27	6	-7		
	Internal Walls and Partitions	6	-5	1		0	0	6	-3		
Finishes	Internal Doors	0	0	0		0	0	0	0		
	Wall Finishes	0	0	0		0	0	0	0		
	Floor Finishes	0	0	0		0	0	0	0		
FF&E	Ceiling Finishes	0	0	0		0	0	0	0		
	FF&E (fixed)	0	0	0		0	0	0	0		
Building Services	FF&E (non-fixed)	0	0	0		0	0	0	0		
	Building services	9	0	0		0	9	0	0		
	Refrigerant Leakage	0	0	0		0	0	0	0		
Prefab	Renewable Electricity Generation	27	0	0		0	55	0	0		
Prefab	Prefab Building Units	0	0	0		0	0	0	0		
Existing	Minor Demolition and Alterations	0	0	0		0	0	0	0		
External	External Works	0	0	0		0	0	0	0		
LETI Total for Option 1		183	-213	25	42	0	49	183	-60		
RIBA Total for Option 1		210	-213	25	42	0	104	183	-60		
All, Option 1		210	-213	25	42	0	104	183	-60		

**RIBA CHALLENGE** (includes ●)

Building Type: Domestic	
Operational Energy	39 kWh/m <sup>2</sup> .a GIA
RIBA level met	2025 Target
Embodied Carbon	351 kg CO <sub>2</sub> e/m <sup>2</sup> GIA
RIBA level met	2030 Target

## User experience

The building has been occupied during holiday times and then, on average, on alternate weekends. It is difficult therefore to provide an accurate energy usage comparison with other similar sized projects that are more frequently occupied. The following has been recorded between October 2021 and October 2022.

Solar PV generated: 2840kWh. (620kg saved)

Total energy consumed: 3020kWh.

The primary take-away is that Passivhaus is proving to be an ideal approach for properties that are not constantly occupied. On arrival, after a couple of weeks away, the internal environment is not 'stale', thanks largely to the MVHR and careful use of zero VOC coatings and materials.

After one heating season the internal temperature could be best described as adequate first thing on a winter morning, but the temperature soon rises to a comfortable level as activities start. Provision has been made for an additional radiator to be installed in the living space should the towel rails prove insufficient, but there are no plans for this at the moment. A further fall back option is installation of an electric heater installed in the MVHR supply air duct.

Although Cumbria is renowned more for rain than sun, the southwest facing glazing does have result in some overheating particularly in Bedroom 1 and the bathroom. Experience has shown this is most simply dissipated or avoided with cross and stack ventilation, particularly when the rooflights are opened.

Overall the internal environmental is supremely comfortable and confirms Passivhaus as the only approach that guarantees comfort and low energy bills.

