

# Project Documentation

## South Devon College Passivhaus



### 1 Photograph



Three bedroom demonstration house at South Devon College, Paignton, UK

### 1.1 Building data

Year of construction	2013	Space heating	<b>15</b> kWh/(m <sup>2</sup> a)
U-value external wall	0.111 W/(m <sup>2</sup> K)		
U-value basement ceiling/floor	0.119 W/(m <sup>2</sup> K)	Primary Energy Renewable	
U-value roof	0.058 W/(m <sup>2</sup> K)	Generation of renewable energy	
U-value window	0.87 W/(m <sup>2</sup> K)	Non-renewable Primary Energy	108 kWh/(m <sup>2</sup> a)
Heat recovery	85%	Pressure test n50	0.6 h-1
Special features	Solar PV		

## 1.2 Brief description of the construction task

South Devon College, as part of a larger project called the South West Energy Centre, commissioned Lacey Hickie Caley Ltd. (LHC) to design a demonstration house on the same site. The original brief was to use the Code for Sustainable Homes Level 5 as the design standard, but the client was persuaded that the Passivhaus Standard would offer a future-proof building.

Rob Rickey was an employee of LHC and a Certified Passive House Designer and produced a compact three bedroom design that would be a familiar product for local housebuilders. The main contractor, Kier, applied themselves to delivering a successful Passivhaus project.

## 1.3 Responsible project participant, certification ID, Passive House Database ID, name and signature of the author of the project documentation

Architect	Rob Rickey, on behalf of Lacey Hickie Caley Ltd.
Implementation planning	Contracts Mgr. Nick Rowe and Project Mgr. Andrew Ash
Building systems	Totus Engineering
Structural Engineering	Hyder Engineering (now Arcadis)
Building Physics	Rob Rickey, on behalf of Lacey Hickie Caley Ltd.
Passive House project planning	Rob Rickey, on behalf of Lacey Hickie Caley Ltd.
Construction management	Kier Group <a href="http://www.kier.co.uk/">http://www.kier.co.uk/</a>
Certifying body	Warm Associates <a href="http://www.peterwarm.co.uk/">http://www.peterwarm.co.uk/</a>
Certification ID	5001
Author of project documentation	Rob Rickey, on behalf of Lacey Hickie Caley Ltd.
Date, Signature	17.11.2016



## 2 Views of SWEC Passivhaus



View from South West showing small balcony



View from South East




View from North




Interior view of ground floor

### 3 Sectional drawing with description – dating from implementation planning




Section showing analysis of solar access and shading. The section also shows the continuity of insulation from the Isoquick foundation insulation, through the walls to the loft. The original design had a warm roof with sloping ceilings, but the form heat loss factor on this fairly small detached house made compliance unnecessarily expensive.

## 4 Floor plans with description




Ground floor plan. The plan form is nearly square, but the stair half-landing projects outside of the simple rectangle. This was a purely architectural decision that gave the house a feature similar to the main building on the same site, but which required additional attention to detailing. The porches are on isolated foundations to reduce thermal bridging.



First Floor Plan. The design is compact, but with attention paid to accessibility standards.

## 5.1 Description of the construction of the floor slab/basement ceiling including insulation




Foundation detail showing Isoquick insulation, concrete slab and alignment of external wall insulation with foundation insulation.




Foundation insulation during installation of damp proof membrane.

## 5.2 Description of the construction of the exterior walls including insulation




The wall construction consists of plasterboard on battens with ProClima Intello airtightness membrane. The structure is double stud construction (270mm) with full-fill glass fibre insulation and 100mm of Isoplaat wood fibre insulation. The exterior finish is timber cladding on battens.

## 5.3 Description of the construction of the roof/top floor ceiling




Roof/wall junction showing continuity of insulation. The ceiling insulation is 600mm of Warmcel cellulose insulation. The original design had the insulation along the roof pitch, but the form heat loss factor was adverse, so the design was changed to a cold roof application.


## 5.4 Description of the window sections including installation drawing




### 5 - WINDOW HEAD



### 4 - WINDOW SILL



## 6 - WINDOW JAMB WITH RENDER



### 3 - PATIO DOOR HEAD/ FIRST FLOOR SILL

The Rational windows have a solid timber frame and outward opening sashes with triple glazing, so although wrapping the external insulation on to the frame would reduce heat loss through the frame, it was not possible. Instead, insulated plasterboard was installed on the inside on the inside, overlapping the frame to reduce thermal bridging.

Window installation details. 1:10 @A3.

Window product: Rational Auraplus; the timber frame U-value is 1.14 average. The triple-glazing U-value is 0.52 and the g value is 0.51.

## 6 Description of the airtight envelope



Air test in progress; smoke pen used to detect leaks

The airtightness layer was mostly created by the use of pro clima Intello membrane on the walls and first floor ceiling. The ground floor airtightness layer was the concrete slab. The membrane was taped to the floor slab, and all of the service penetrations were through the slab in one area, which was easier to test for leaks.


The testing was carried out by Steve Simmonds of Watgate Services Ltd.

 <b>WATERGATE</b>	 <b>WATERGATE</b>																
<b>Certificate of Building Air Leakage</b>	<b>Test Data backup</b>																
<p>This is to certify that</p> <p><b>SWEC Passivhaus</b>  <b>South West Energy Centre</b>  <b>South Devon College</b>  <b>Long Road</b>  <b>Paignton, TQ4 7RZ</b></p> <p>Tested for on 26 July 2013  <small>M888918d</small> in accordance with Passivhaus requirements          achieved a performance of</p> <p><b>0.575 Air Changes/Hour</b>  <b>(Average of Positive &amp; Negative Tests)</b></p> <p>Certificate Number: <b>Wgt/ssl/260713</b>          Awarded by: Steve Simmonds      Date: 26 July 2013          Signed: <i>SS</i></p>	<table border="1"> <thead> <tr> <th>Test Stage</th> <th>Negative Pressure</th> <th>Positive Pressure</th> <th>Mean Result</th> </tr> </thead> <tbody> <tr> <td>Stage 1</td> <td>0.56</td> <td>0.48</td> <td>0.52</td> </tr> <tr> <td>Stage 2</td> <td>0.57</td> <td>0.51</td> <td>0.54</td> </tr> <tr> <td>Stage 3</td> <td>0.61</td> <td>0.54</td> <td>0.575</td> </tr> </tbody> </table>	Test Stage	Negative Pressure	Positive Pressure	Mean Result	Stage 1	0.56	0.48	0.52	Stage 2	0.57	0.51	0.54	Stage 3	0.61	0.54	0.575
Test Stage	Negative Pressure	Positive Pressure	Mean Result														
Stage 1	0.56	0.48	0.52														
Stage 2	0.57	0.51	0.54														
Stage 3	0.61	0.54	0.575														
<p>Watergate Services Limited          Unit 6, Teignbridge Business Centre, Heathfield, Newton Abbot          Devon          TQ12 6TZ, UK          Tel: +44 (0) 7525 779616 Fax: +44 (0) 1626 830891  <a href="http://www.watgateservices.co.uk">www.watgateservices.co.uk</a></p>	<p>Watergate Services Limited          Unit 6, Teignbridge Business Centre, Heathfield, Newton Abbot          Devon          TQ12 6TZ, UK          Tel: +44 (0) 7525 779616 Fax: +44 (0) 1626 830891  <a href="http://www.watgateservices.co.uk">www.watgateservices.co.uk</a></p>																

## 7.1 Description of the planning of the ventilation ductwork



The MVHR unit was located centrally on the ground floor, in the open plan area so it would be visible for teaching purposes. There was an extract valve at the kitchen area, the wc and the bathroom upstairs. The supply ductwork upstairs was taken to the wall next to the bedroom doors and Coanda valves used to reduce duct runs. Design was by the Green Building Store, as shown in the design drawings below.



Cad layouts showing implementation (Green Building Store)

## 7.2 Description of the planning for the central unit



The MVHR unit was a Paul Novus, sized to accommodate teaching groups, not just a family. The effective heat recovery efficiency is 85%. The electrical efficiency is 0.24 Wh/m<sup>3</sup>

The Unit was located centrally on an outside wall, and in view of visitors so it can be used as a teaching aid.

### STANDARD INPUT FOR BALANCED VENTILATION

#### Ventilation dimensioning for systems with one ventilation unit

Occupancy	m <sup>2</sup> /P	35				
Number of occupants	P	2.3				
Supply air per person	m <sup>3</sup> /(P·h)	30				
Supply air requirement	m <sup>3</sup> /h	69				
Extract air rooms				Bathroom		
Quantity			Kitchen	Bathroom	(shower only)	WC
Extract air requirement per room	m <sup>3</sup> /h		1	1		1
Total Extract Air Requirement	m <sup>3</sup> /h		60	40	20	20
	m <sup>3</sup> /h		120			
Design air flow rate (maximum)	m <sup>3</sup> /h		120			

**Average air change rate calculation**

Type of operation	Daily operation duration h/d	Factors referenced to maximum	Air flow rate m <sup>3</sup> /h	Air change rate 1/h
Maximum		1.00	120	0.64
Standard	24.0	0.77	92	0.49
Basic		0.54	65	0.34
Minimum		0.40	48	0.25
	<b>Average value</b>	<b>0.77</b>	<b>Average air flow rate (m<sup>3</sup>/h)</b>	<b>Average air change rate (1/h)</b>
			<b>92</b>	<b>0.49</b>

Extract from PHPP showing overall ventilation calculation

## 8 Description of the heat supply system

Heating is provided by two small electrical radiator units (no photo available)

## 9 Brief documentation of important PHPP results

Building:	South Devon College Demonstration House		
Street:	Long Road		
Partcode/City:	TQ4 7BL	Paignton	
Country:	UK		
Building Type:	Dwelling		
Climate:	South West (Exeter Airport)		
Name Owner(s) / Client(s):	South Devon College		
Street:	Long Road		
Partcode/City:	TQ4 7BL	Paignton	
Architect:	Lacey Hickie & Caley Ltd		
Street:	The Design Studio, Emperor Way		
Partcode/City:	EX1 3QS	Exeter	
Mechanical System:	Totus Engineering Ltd		
Street:	Splatford Barton		
Partcode/City:	EX6 7XY	Exeter	
Year of Construction:	2013	Interior Temperature:	20.0 °C
Number of Dwelling Units:	1	Internal Heat Gain:	2.1 W/m <sup>2</sup>
Enclosed Volume V <sub>encl</sub> :	359.0		
Number of Occupants:	2.3		

Specific building demands with reference to the treated floor area		req: Monthly method	
		Requirements	Fulfilled?*
<b>Space heating</b>	Treated floor area	80.3 m <sup>2</sup>	
	Annual heating demand	15 kWh/(m <sup>2</sup> a)	15 kWh/(m <sup>2</sup> a) <b>yes</b>
	Heating load	12 W/m <sup>2</sup>	10 W/m <sup>2</sup> -
	Frequency of overheating (> 25 °C)	1.3 %	-
<b>Primary Energy</b>	Space heating and cooling, dehumidification, DHW, Auxiliary Electricity and Household Electricity	108 kWh/(m <sup>2</sup> a)	120 kWh/(m <sup>2</sup> a) <b>yes</b>
	DHW, space heating and auxiliary electricity	74 kWh/(m <sup>2</sup> a)	-
<b>Airtightness</b>	Pressurisation test result n <sub>50</sub>	0.6 1/h	0.6 1/h <b>yes</b>

\* empty field: data missing; ?? as required

<b>Passive House?</b>	<b>yes</b>
-----------------------	------------

### 10.1 Overall construction costs:

### 10.2 Building costs

1858 €/m<sup>2</sup> Treated Floor Area according to PHPP