Certificate

Certified Passive House Component Valid until 31 December 2025

Category:	Ventilation unit with heat recovery and heat pump (combi unit)
Manufacturer:	Zhejiang Dpurat Environmental Equipment Co., Ltd. Baita Industrial Gathering Area,Xianju County,Taizhou,Zhejiang China

Product name: DBDF-35B-15D-DH

This certificate was awarded based on the following criteria for ventilation part:

Thermal comfort	$\theta_{supply air} \ge 16.5 \ ^{\circ}C$
	at θ _{outdoor air} = -10 °C
Effective heat recovery rate	<mark>n_{HR,eff} ≥ 75 %</mark>
Electric power consumption	P _{el} ≤ 0.45 Wh/m³
Airtightness	Interior and exterior air leakage rates less than 3 % of nominal air flow rate
Balancing and adjustability	Air flow balancing possible: yes Automated air flow balancing: yes
Sound insulation	Sound level $L_w \le 35$ dB(A) not met Unit should be installed so that it is acoustically separated from living areas
Indoor air quality	Outdoor air filter at least F7 Extract air filter at least G4
Frost protection	Frost protection for the heat exchanger with continuous fresh air supply down to θ _{outdoor air} = -15 °C

This certificate was awarded based on the following criteria for heat pump part: (limit values for final energy consumption):

Space heating Space cooling (humid climate): Space cooling (dry climate): 9 kWh/(m²y) 13 kWh/(m²y) 11 kWh/(m²y)

1697ch00

Further information can be found in the appendix of this certificate.

www.passivehouse.com

Passive House Institute Dr.Wolfgang Feist 64283 Darmstadt Germany

> Certified for air flow rates of 140-160 m³/h

> Winter performance of ventilation η_{HR,eff:} 76 % η_{MR,eff:} 66 % Pel: 0.30 Wh/m³

Summer performance of ventilation η_{HR,eff:} 54 % η_{MR,eff:} 76 % Pel: 0.30 Wh/m³

Performance of heat pump

Heating 6.7 kWh/(m²y)

Cooling DRY 6.3 kWh/(m²y)

Cooling WET 8.7 kWh/(m²y)



Appendix to the certificate, Zhejiang Dpurat Environmental Equipment Co., Ltd.

Manufacturer: Zhejiang Dpurat Environmental Equipment Co., Ltd. Baita Industrial Gathering Area,Xianju County,Taizhou,Zhejiang China Email: <u>360538810@qq.com</u> Tel: 0086+0576-89379233 Contact: Zhang Ling-yun

Part 1: Ventilation unit

Passive House comfort criterion

A minimum supply air temperature of 16.5 °C is maintained at an outdoor air temperature of -10 °C.

Efficiency criterion (heat recovery rate)

The effective dry heat recovery rate is measured at the test facility using balanced mass flows on the outdoor air/extract air side. The boundary conditions for the measurement should be taken from the documents relating to the testing procedure.

$$\eta_{\text{HR,eff}} = \frac{(\vartheta_{ETA} - \vartheta_{EHA}) + \frac{P_{el}}{m.c_p}}{(\vartheta_{ETA} - \vartheta_{ODA})}$$

The (dry) ventilation heating load (the house is the system boundary) can be calculated using $\eta_{\text{HR,eff}}$ based on the formula $\dot{V}_{\text{supply_air}} (1-\eta_{\text{HR,eff}}) = 0.34 + \Delta \vartheta$ (multiplied by the infiltration rate). The rates of heat recovery are usually greater if condensation occurs in the heat exchanger. Initially, this will not be taken into account on purpose. For this device the numbers are as follows:

Efficiency criterion (power consumption)

The overall electrical power consumption of the device including that for regulation, but without that for the frost protection heating, is tested at the test facility at an external pressure of 100Pa (50Pa for each of the pressure/intake sides).

For this device:

0.30 (0.30) Wh/m³

Air tightness and insulation

Before starting the thermodynamic test, the air tightness test should be carried out for under pressure as well as for over pressure. The leakage air flows must not be greater than 3 % of the average air flow volume of the operating range of the ventilation device.

The following result was obtained for the device being tested according to DIBt guidelines:

Internal leakage: 2.8 %

External leakage: 1.3 %

This ventilation unit meets the airtightness requirements.

www.passivehouse.com

Appendix to the certificate, Zhejiang Dpurat Environmental Equipment Co., Ltd.

Adjustability

It must be possible to adjust the balance between the exhaust air flow rate and the outdoor air flow rate for all units.

- This unit is certified for air flow rates of 140-160 m³/h
- Balancing the air flow rates of the unit is possible
 - ✓ The air flow rates are hold steady automatically
- The users should have at least have following possibilities for adjustment:
 - ✓ Switching the system on and off
 - ✓ Synchronized adjustment of the supply air and extract air flow to basic ventilation (= 70-80 %), standard ventilation (= 100 %) and increased ventilation (= 130 %) with clear readability of the set status.
 - ✓ Depending on the demand, the user can choose between several operating levels that can be set manually at the control unit of the operating element.
- The device being tested here has a standby power consumption of **6.8 W** and therefore does not comply with the target value of 1 W. The device must be equipped with an additional external switch to separate the device from the electric circuit if required.
- After a power failure the device automatically continues to operate in the mode that was set before the power failure.

Acoustical testing

In order to restrict the sound pressure level in the installation room, the sound power level emission should be restricted to 35 dB(A). With an equivalent room absorption area of 4 m² the amounts of sound power level and sound pressure level are nearly the same (the exact value of the sound pressure level in the specific installation room can be calculated with the help of the sound protection tool (download on <u>www.passivehouse.com</u>)).

Installation instructions must be provided which describe how the sound level can be kept below 25 dB(A) in living areas and below 30 dB(A) in functional areas.

The sound measurements for the unit DBDF-35B-15D-DH <u>have not been carried out</u> yet. This should be done as soon as possible to give designers and builders a better idea about the detailed design and noise reduction of silencers which need to be installed.

The sound level of the unit <u>can be expected to exceed</u> the limit value of 35 dB(A). Therefore the unit should be installed so that it is acoustically separated from living areas. It can be also expected that silencers need to be installed in supply and extract air streams.

Indoor air hygiene

Inspection and cleaning of the central device including the heat exchanger is simple. The filter can be replaced by the user himself/herself (no specialist required). The unit is equipped with following filter qualities:

- ✓ Outdoor Air filter H11
- ✓ Extract Air filter G4

If the device is not operated during the summer, the filter should be replaced before the next operation.

Filter replacement is recommended after an interval of 6 months. However, depending on environment in where the unit will operate, more often changes can be required.

www.passivehouse.com

Appendix to the certificate, Zhejiang Dpurat Environmental Equipment Co., Ltd.

Frost protection

Appropriate measures should be taken to ensure prevention of icing over of the heat exchanger and freezing up of hydraulic post-heater coils during extreme winter temperatures (-15°C). The regular functioning of the device should be permanently ensured during uninterrupted operation of the frost protection circuit (there is no interrupt circuit for outdoor air in the Passive House, as the heating loads caused by the forced infiltration would become too high). If heater coils for hot water are used, a suitable frost protection circuit should ensure prevention of frost damage to these heater coils. In the process, the possibility of failure of the pre-heating coils and extract air fans must also be taken into consideration.

- Frost protection circuit for the heat exchanger:
 - ✓ The frost protection of heat recovery unit is done by use of resistance direct electricity heater.
- Frost protection circuit for downstream hydraulic heater coils:
 - ✓ The unit is equipped with heat pump technology, which ensures the frost protection of heater coils.

It should be noted that cold air can also lead to freezing up of stationary fans due to free circulation; this can only be ruled out if the air duct is closed (by means of a shut-off flap).

Abbreviations

- AU/ODA = Outdoor air
- FO/EHA = Exhaust air
- ZU/SUP = Supply air
- AB/ ETA = Extract air

Part 2: Heat pump

The seasonal performance of tested unit is evaluated by the Passive House Institute for representative climates. This is based on the key characteristics determined for space heating, cooling and dehumidification operating modes at all test points specified in the testing regulations and stated in the certificate.

The Passive House Institute uses three reference climates, first for heating (cool,temperate), second for sensible cooling (hot and dry), and third for sensible cooling and dehumidification (hot and humid). This forms the basis for the calculation of the energy balance. Evaluation is based on final energy consumption. The limiting values for final energy consumption are 13 kWh/(m²y) for sensible/latent cooling (humid climate) and 9 kWh/(m²y) for heating. For cooling in dry climate, the limit for final energy is 11 kWh/(m²y).

Verification is based on a model Passive House with a heating demand of 15 kWh/(m²y), cooling demand for humid climate 23 kWh/(m²y) and cooling demand for dry climate 22 kWh/(m²y). All calculations are based on hourly method.

The certified range for heat pump matches the certified range for ventilation unit. The following relation between air flow rate and floor area has been used for reference building: $35 \text{ m}^2/\text{person}$, $30 \text{ m}^3/(\text{h.person})$. Based on this relation, the heat pump is certified for floor area of 140-160 m². If the unit is to be used in flats with smaller floor area than that, this can result in worse performance (it very much depends on control/regulation system of the particular unit. The performance of control system was not evaluated during certification).

Air flow rate of recirculation air used during measurements in laboratory was 400 m³/h.

During the defrost operation, the temperature of supply air was below comfort limit of 16.5°C. According to statement of producer, the supply of fresh air during defrost mode can be deactivated in case this would cause discomfort.

Dehumidification function

The unit DBDF-35B-15D-DH is controlled not only based on room temperature but <u>also based on room humidity</u>. The unit is <u>also equipped with second coil</u> which is used for reheating of dehumidified air (being undercooled as a result of dehumidification process because dew point temperature has to be reached on surface of the cooling coil to provide dehumidification). The tested SHR (sensible heat ratio) was as low as 0.1. The reheating is done by use of heat pump. Note: when this reheating function was activated, the achieved available latent cooling capacity is reduced by 25%. The COP for reheating function is 3.3.

Performance values of heat pump

Heating

Temperature (°C)		Capacity (kW)			COP		
outside	room	On/OFF	ON/OFF Limit	Max	On/OFF	ON/OFF Limit	Max
-7	20	0.53	1.31	3.36	1.33	2.19	1.98
2	20	0.51	1.26	3.23	1.81	2.98	2.70
7	20	0.61	1.51	3.88	2.25	3.71	3.36

Cooling

Temperature (°C)		Capacity (kW)			EER		
outside	room	On/OFF	ON/OFF Limit	Max	On/OFF	ON/OFF Limit	Max
35	25	0.80	1.58	3.78	2.43	3.20	3.43
30	25	0.83	1.63	3.90	2.80	3.70	3.96
25	25	0.77	1.52	3.63	2.85	3.77	4.03